



JOHN ANDERSON, Jr. Governor
 RICHARD C. BYRD Chairman
 ALVIN F. GRAUERHOLZ Commissioner
 HARRY G. WILES Commissioner
 RAYMOND B. HARVEY Secretary
 CHARLES C. McCARTER Gen. Counsel

State Corporation Commission
 CONSERVATION DIVISION
 (Oil, Gas and Water)
 500 Insurance Bldg. 212 N. Market
 WICHITA, KANSAS

VERBAL PERMIT FORM
 (To Be Filed By Plugging Agent)

J. P. Roberts
 Assistant Director
 500 Insurance Building
 212 North Market
 Wichita 2, Kansas

Dear Sir:

Mr. Nix of Skelly Oil Co. has this

date requested permission to plug the following described well:

Mr. Nix guarantees payment of the plugging fee.

Operator's full Name: Skelly Oil Co.

Complete Address: Box 649 McCook, Nebraska

Lease Name: Mohler Well No. # 2

Location: NW NW NW Sec. 2 Twp. 34 Rge. 29 (E) (W)

County Meade Total Depth 5880' Oil Well

Gas Well Input Well SWD Well D & A Lost Hole

Mr. Nix was instructed to plug the well as follows:

8 5/8"-1448' Circulated w/cement. 5 1/2"-5880' Cemented. Plug back to 5795'

Top perforations 5712' Plug bottom w/30 Sax. cement top cement-4780'

Mud 4780' to 690' 35 Sax. cement 690' to 590'

Mud 590' to 45' 50 Sax. cement 45' to 0

RECEIVED
 STATE CORPORATION COMMISSION

NOV 30 1965

CONSERVATION DIVISION
 WICHITA, KANSAS

Very truly yours,

[Signature]
 Conservation Division Agent