

State of Kansas



# State Corporation Commission

## CONSERVATION DIVISION

(Oil, Gas and Water)  
500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS 67202

### VERBAL PERMIT FORM (To Be Filed By Plugging Agent)

RECEIVED  
STATE CORPORATION COMMISSION

AUG 21 1974

CONSERVATION DIVISION  
Wichita, Kansas

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Dear Sir:

Mr. Trigg of Trigg has this

date requested permission to plug the following described well:

Mr. Trigg guarantees payment of the plugging fee.

Operator's full Name: Trigg Exploration

Complete Address: 1942 Broadway, Boulder, Colorado 80302

Lease Name: Borchers Well No. 1-1

Location: NE SW Sec. 1 Twp. 34 Rge. 29 XX (E)(W)

County: Meade Total Depth 4610' Oil Well X

Gas Well      Input Well      SWD Well      D & A      Lost Hole     

Mr. Trigg was instructed to plug the well as follows:

8 5/8" to 1534' circulated w/ cement. 4 1/2" to 4590' cemented.


Top perforations 3060' Plug bottom w/ 15 sacks cement.

Top of cement 2863' Mud 2863' to 900'

Spot 30 sacks cement 900' to 800' Mud 800' to 40'

Plug, Hulls & 10 sacks cement 40' to 0'.

Very truly yours,

  
Conservation Division Agent