



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

P. O. Box 17027 3830 S. Meridian
WICHITA, KANSAS 67217

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Bill Hair of Alpar Resources, Inc. has this
date requested permission to plug the following described well:

Mr. Bill Hair guarantees payment of the plugging fee.

Operator's full Name: Alpar Resources, Inc.

Complete Address: Box 906, Perryton, Texas 79070

Lease Name: B. W. Borchers Well No. 1

Location: 2310' FNL 1420' FEL Sec. 1 Twp. 34 Rge. (E)(W) 29

County: Meade Total Depth 5800' Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Hair was instructed to plug the well as follows:

8-5/8" surface casing set at 1334' cemented to surface. Filled hole
with heavy mud to 1330'. Set plug and displaced 50 sacks cement through
drill pipe. Mud to 35'. Set plug. Filled with 15 sacks of cement
to base of cellar.

Very truly yours,

Frank Bradford
Conservation Division Agent