

State of Kansas



JOHN CARLIN  
R. C. LOUX  
JANE T. ROY  
PHILLIP R. DICK  
CAROL J. LARSON

Governor  
Chairman  
Commissioner  
Commissioner  
Executive Secretary

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

200 Colorado Derby Building  
WICHITA, KANSAS 67202

RECEIVED  
STATE CORPORATION COMMISSION  
JUN 29 1982  
CONSERVATION DIVISION  
Wichita Kansas

VERBAL PERMIT FORM  
(To be filed by Plugging Agent)

Dear Sir:

Mr. Roger Feldman of De Moch Drilling Co. has this date requested permission to plug the following described well:

Operator's Full Name: Mesa Petroleum Co.

Complete Address: Box 18950 Oklahoma City, Okla., 73154

Lease Name: Bannagree Well No. 1-29

Location: 1980' FSL - 1980' FWL Sec. 29 Twp. 34 Rge. 28 (E) (W)

County: Meade Total Depth: 5544'

Abandoned Oil Well  Gas Well  Input Well  SWD Well  D&A

Other well as hereafter indicated: \_\_\_\_\_

Mr. Feldman was instructed to plug the well as follows:

They cement circulated 1506' of 8 5/8" surface casing. The anhydrite was topped at 1340'. 1st plug at 1550' with 60 lbs of cement. 2nd plug at 750' with 30 lbs of cement, 3rd plug at 40' to 0' on solid bridge with 10 lbs of cement. Then they circulated 10 lbs of cement in each the rat hole & mouse hole. The cement was pumped through drill pipe

Very truly yours, (over)

Paul A. Luther  
Conservation Division Agent

with hole full of heavy mud. The plugging was  
accomplished by Halliburton Co

Paul Lattis