

State of Kansas



JOHN ANDERSON, Jr. Governor
WILLIAM L. MITCHELL Chairman
ALVIN F. GRAUERHOLZ Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
ROBT. C. LONDERHOLM Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION

JAN 6 1965

CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

Dear Sir:

Mr. Duane Born of Chem-Tech Service Inc. has this date requested permission to plug the following described well:

Mr. Born guarantees payment of the plugging fee.

Operator's full Name: Imperial Oil of Kansas, Inc.

Complete Address: 780 Fourth National Bldg., Wichita, Kansas

Lease Name: Meredith Well No. # 1

Location: C NW SE Sec. 28 Twp. 34 Rge. 28 (E) (W) W

County Meade Total Depth 3325 Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Born was instructed to plug the well as follows:

1350' of 7" surface pipe, cement circulated with 450 sacks.

Fill hole with drilling mud, spot 35 sacks of cement at 700'.

Fill hole with drilling mud to 45', set bridge plug on fluid at 45', and cement with 15 sacks to the base of the cellar.

Very truly yours,

Archie Elving
Conservation Division Agent