

DISTRICT CONSERVATION AGENT'S REPORT



TO:

State Corporation Commission  
Conservation Division  
800 Bitting Building  
Wichita, Kansas

FILE NO. 31-40

LOCATION C NE SW

SEC. 23 TWP. 33 RGE. 31W

Dry Hole          Abandoned Oil Well X Abandoned Gas Well         

I have today completed supervision of plugging of:

Well No. 1 Lease C. C. Wheatley

Operator Stanolind Oil & Gas Co. Address Ulysses, Kansas

Field                                  County Seward

Total Depth 7340 Feet.

(Describe briefly the manner in which the well was plugged)

July 31, 1952 - Plugged back with sand from 4950' to 4854'.

August 1, 1952 - Plugged back with 5 sacks cement with bailer from  
4854' to 4829'. Shut down August 2 and 3. August 4, shot 5 1/2" casing  
off @ 3806, 3715 and 3624. August 5, 1952 shot 5 1/2" casing off at  
3379', 3190', 3001' and 2788'. Pulled 12 jts. of 5 1/2" casing. August  
6, 1952 pulled 77 jts. of 5 1/2" casing. August 7, 1952 30 sacks  
mud pumped in well, set top plug @ 45', capped with 15 sacks cement.

**PLUGGING**  
 RECEIVED  
 STATE CORPORATION COMMISSION  
 AUG 23 1952  
 CONSERVATION DIVISION  
 Wichita, Kansas

K. J. Phillips  
 District Conservation Agent  
 Date 8-7-52