

RECEIVED
STATE CORPORATION COMMISSION

15-175-10202-0000

JUN 2 1960

CONSERVATION DIVISION
Wichita, Kansas STATE CORPORATION COMMISSION

KANSAS

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

MAY 20 1960

CONSERVATION DIVISION
Wichita, Kansas

TO:
Jewel M. Ogden, Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

File No. _____ County: Sevau

Location: C SW Sec. 17 Twp. 33 Rge. 34 (E) (W)

Name of Field: _____ Total Depth: 6339

I have this date completed supervision of plugging of:

Lease Name: M. M. Mair Well No. 1-17

Operator's Full Name: Panhandle Eastern Pipe Line Co.

Complete Address: Box 979, Liberal, Kans.

Plugging Contractor: Dale Well Servicing

Address: Boyer Texas License No. _____

Oil Well _____ Gas Well Input Well _____ SWD Well _____ D & A _____

Other well as hereafter indicated: _____

Was any delay in plugging operations caused by Conservation Division Agent? Yes _____ No

If yes how long? _____ Reason: _____

Operation Completed: Hour 5 pm Day 17 Month May Year 1960

The above well was plugged as follows:

595' of 13 3/8" surface casing. Top perf 5878'. Pumped 50
sack cement on bottom to 5780'. Pulled 2740' of 5 1/2"
hole filled to 595' with heavy mud. Rock bridge from 595' to
585'. 50 sack cement dumped on bridge. Mud to 30'
10' rock bridge to 30'. Cement dumped to base of collar.

Signed: [Signature]
Conservation Division Agent

Reviewed: J. Lewis Brock
Field Supervisor

Remarks: 11 1/2
days

INVOICED
DATE 6/6/60
INV. NO. 1466-2