

KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Administrator
500 Insurance Building
212 North Market
Wichita 2, Kansas

RECEIVED
STATE CORPORATION COMMISSION

JUN 1 1965

CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Anadarko Prod.Co.

Complete Address: Box 351 Liberal, Kansas

Lease Name Morlan Well No. A-2

Location C NE SW Sec. 21 Twp. 33S Rge. 34 (E) (W)

County Seward Total Depth 6303'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated:

Plugging Contractor: Sargent Casing Pulling

Address: Liberal, Kansas License No. 511

Operation Completed: Hour 4 PM Day 27 Month 5 Year 65

The Above well was plugged as follows:

8 5/8"-1652' Circulated w/cement. 4 1/2"-4293' Cemented. Top perforations-4293'

Plug bottom w/20 Sax.cement top cement 3850' Mud 3850' to 700'

Spotted 35 Sax.cement 700' to 600' Mud 600' to 45'

Plug, 15 Sax.cement 45' to 0 Company Pump. Pulled 2694' 4 1/2" pipe.

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 6/1/65

INV. NO. 1238-W

Signed: [Signature]
Well Plugging Supervisor