

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION  
JUN 28 1971  
CONSERVATION DIVISION  
Wichita, Kansas

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Operator's Full Name Leben Oil Corporation

Complete Address Box 486, Great Bend, Kansas

Lease Name Etzold Well No. 1

Location C NE SW Sec. 22 Twp. 33 Rge. 34 (E) (W)

County Seward Total Depth 6494'

Abandoned Oil Well  Gas Well X Input Well  SWD Well  D & A X

Other well as hereafter indicated None

Plugging Contractor Sargents Casing Pulling Co.

Address Box 506, Liberal, Kansas License No. 511

Operation Completed: Hour 4:00Pm Day 26 Month 6 Year 1971

The above well was plugged as follows:

8 5/8" to 1647' circulated w/ cement. 4 1/2" to 6434' cemented.

Top perforations 6380' Casing parted at 3600'

Plug bottom w/ 30 sacks cement. Top of cement 2400'

Mud 2400' to 900' Spotted 35 sacks cement 900' to 800'

Mud 800' to 45' Plug, Hulls & 15 sacks cement 45' to 0'.

Company Pump Pulled 2531' of 4 1/2" casing.

I hereby certify that the above well was plugged as herein stated.

Signed: *Edward J. ...*  
Well Plugging Supervisor

INVOICED

DATE 6/30/71  
INV. NO. 3918-W