

KANSAS

V
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
JUL 12 1971
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name Mobil Oil Corp.

Complete Address Box 400, Hugoton, Kansas 67951

Lease Name Shafer Well No. 1

Location C SW Sec. 5 Twp. 33 Rge. 38 (E) (W)

County Stevens Total Depth 2708'

Abandoned Oil Well _____ Gas Well X Input Well _____ SWD Well _____ D & A X

Other well as hereafter indicated None

Plugging Contractor J.D. Well Service

Address Liberal, Kansas License No. 632

Operation Completed: Hour 2:00PM Day 2 Month 7 Year 1971

The above well was plugged as follows:

12 1/2" to 550' circulated w/ cement. 8 5/8" to 2549' circulated w/ cement

7" liner 2435' to 2708' Plug bottom w/ 50 sacks cement

Top of cement 2285' Mud 2285' to 623'

Spotted 35 sacks cement 623' to 500' Mud 500' to 60'

Plug, bulls & 15 sacks cement 60' to 0'. Halliburton Pump Truck.

No Pipe Pulled

I hereby certify that the above well was plugged as herein stated.

Signed: *Edward J. Lewis*
Well Plugging Supervisor

INVOICED

DATE 7/14/71

INV. NO. 3988-2