

KANSAS

Form CP-3
Rev. 6-4-68

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

DEC - 8 1980

J. Lewis Brock
Administrator
245 North Water
Wichita, KS 67202

Authority Act 221980
API Number 15 - -
CONSERVATION DIVISION
Wichita (of Kansas well)

Operator's Full Name Cuties Service Company
Complete Address 3543. NW. 58th St. Okla City Okla.
Lease Name Barnett "A" Well No. 2
Location C. 58 1/4 Sec. 8 Twp. 34 Rge 35 (E) (W) 4
County Stevens Total Depth 6710
Abandoned Oil Well Gas Well Input Well _____ SWD Well _____ D & A _____
Other well as hereafter indicated _____
Plugging Contractor Toland & Johnson
Address Okla City, Okla. License No. _____
Operation Completed: Hour 3:00 PM Day 4th Month Dec Year 1980

The above well was plugged as follows:

There was 1763' of 8 1/8" surface casing C.C.
5 1/2" was set to 6560'. Perforations were
6458-6450'. Set cast iron bridge plug at 6410
with 1 Shs cement. 1st plug at 3250-3119
with 50 Shs cement. 2nd plug at 1797-1637
with 50 Shs cement. 3rd plug at 804-734
with 75 Shs cement 4th plug at 40-0 with
15 Shs cement. There was 3500' of 5 1/2" salvaged.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Chance Thomas
Well Plugging Supervisor

DATE 1-12-81

INV. NO. 3887-W