

**UNITED STATES
DEPARTMENT OF THE INTERIOR
BUREAU OF LAND MANAGEMENT**

SUBMIT IN DUPLICATE*

(See other instructions on reverse side)

FOR APPROVED
OMB NO. 1004-0137
Expires: December 31, 1991

CORR

WELL COMPLETION OR RECOMPLETION REPORT AND LOG*

1a. TYPE OF WELL: OIL WELL GAS WELL DRY Other _____

b. TYPE OF COMPLETION: NEW WELL WORK OVER DEEP-EN PLUG BACK DIFF. RENVR. Other _____

2. NAME OF OPERATOR
Anadarko Petroleum Corporation

3. ADDRESS AND TELEPHONE NO.
P. O. Box 351, Liberal, Kansas 67905-0351 (316) 624-6253

4. LOCATION OF WELL (Report location clearly and in accordance with any State requirements)*
At surface 660' FSL & 660' FWL
At top prod. interval reported below Same
At total depth Same

14. PERMIT NO. DATE ISSUED
15-129-211440000 10-15-92

5. LEASE DESIGNATION AND SERIAL NO.
KS NM 67011
6. IF INDIAN, ALLOTTEE OR TRIBE NAME
7. UNIT AGREEMENT NAME
8. FARM OR LEASE NAME, WELL NO.
USA "K" No. 2
9. API WELL NO.
15-129-211440000
10. FIELD AND POOL, OR WILDCAT
Sitrrup
11. SEC., T., R., M., OR BLOCK AND SURVEY OR AREA
Sec. 2-33S-40W

12. COUNTY OR PARISH Morton 13. STATE Kansas
15. DATE SPUNDED 11-3-92 16. DATE T.D. REACHED 11-13-92 17. DATE COMPL. (Ready to prod.) 12-9-92 18. ELEVATIONS (DF, RKB, RT, GR, ETC.)* 3271.4 GR 19. ELEV. CASINGHEAD NA

20. TOTAL DEPTH, MD & TVD 5680 21. PLUG, BACK T.D., MD & TVD 5524 22. IF MULTIPLE COMPL., HOW MANY* NA 23. INTERVALS DRILLED BY ROTARY TOOLS X CABLE TOOLS

24. PRODUCING INTERVAL(S), OF THIS COMPLETION—TOP, BOTTOM, NAME (MD AND TVD)* 5276-81 Morrow 25. WAS DIRECTIONAL SURVEY MADE Yes

26. TYPE ELECTRIC AND OTHER LOGS RUN DIL/SFL/GR; CNL/LDT/GR; Microlog; Dipmeter 27. WAS WELL CORDED No

28. CASING RECORD (Report all strings set in well)

CASING SIZE/GRADE	WEIGHT, LB./FT.	DEPTH SET (MD)	HOLE SIZE	TOP OF CEMENT, CEMENTING RECORD	AMOUNT PULLED
8 5/8	24#	1547	12 1/4	525 sxs Com/200 sxs Poz/Surf	0
5 1/2	15.50#	5591	7 7/8	50 sxs Poz/260 sxs thixset	0
	FO Tool	2622		160 Pozmix	

29. LINER RECORD

SIZE	TOP (MD)	BOTTOM (MD)	SACKS CEMENT*	SCREEN (MD)
None				

30. TUBING RECORD

SIZE	DEPTH SET (MD)	PACKER SET (MD)
2 3/8	5267	None

31. PERFORATION RECORD (Interval, size and number)

5276-5281 - 4 SPF = 20 Total Shots

32. ACID, SHOT, FRACTURE, CEMENT SQUEEZE, ETC.

DEPTH INTERVAL (MD)	AMOUNT AND KIND OF MATERIAL USED
5276-5281	A/600 gals 7 1/2% fe acid.

33. PRODUCTION

DATE FIRST PRODUCTION	PRODUCTION METHOD (Flowing, gas lift, pumping—size and type of pump)	WELL STATUS (Producing or shut-in)
12-9-92	Flowing	Producing

DATE OF TEST	HOURS TESTED	CHOKES SIZE	PROD'N. FOR TEST PERIOD	OIL—BBL.	GAS—MCF.	WATER—BBL.	GAS-OIL RATIO
12-13-92	24	NA	→	67	339	-	5059

FLOW, TUBING PRESS.	CASING PRESSURE	CALCULATED 24-HOUR RATE	OIL—BBL.	GAS—MCF.	WATER—BBL.	STABILITY (API CORR.)
160	450	→	67	339	-	41.2

34. DISPOSITION OF GAS (Sold, used for fuel, vented, etc.) Sold TEST WITNESSED BY

35. LIST OF ATTACHMENTS
KCC ACO-1, Electric Logs, Cement Tickets, Drillers Log, Etc.

36. I hereby certify that the foregoing and attached information is complete and correct as determined from all available records

SIGNED Beverly J. Williams TITLE Engineering Technician DATE 12-30-92

*(See Instructions and Spaces for Additional Data on Reverse Side)

Title 18 U.S.C. Section 1001, makes it a crime for any person knowingly and willfully to make to any department or agency of the United States any false, fictitious or fraudulent statements or representations as to any matter within its jurisdiction.

RECEIVED
CORPORATION COMMISSION
FEB 8 1993
CONSERVATION DIVISION
Wichita, Kansas

37. SUMMARY OF POROUS ZONES: (Show all important zones of porosity and contents thereof; cored intervals; and all drill-stem, tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries):

38.

GEOLOGIC MARKERS

FORMATION	TOP	BOTTOM	DESCRIPTION, CONTENTS, ETC.	NAME	TOP	
					MEAS. DEPTH	TRUE VERT. DEPTH
				Sand & Redbed	0	
				Glorietta Sand	1096	
				Redbed	1211	
				Lime-Shale	2291	

6-65

LEP
 10000 10000 10000
 10000 10000 10000

ATTACHMENT

USA "K" No. 2
Section 2-33S-40W
Morton County, Kansas

<u>NAME</u>	<u>TOP</u>
B/Stone Corral	1560
Chase	2254
Krider	2282
Winfield	2325
Towanda	2383
Ft. Riley	2447
Florence	2494
Council Grove	2552
Admire	2802
Wabaunsee	2986
Topeka	3228
Heebner	3716
Toronto	3728
Lansing	3812
Kansas City	4200
Marmaton	4490
Cherokee	4644
Morrow	5080
Morrow "D" Top	5240
Morrow "D" Base	5282
L. Morrow	5391
Keyes	5519
Ste. Genevieve	5612
TD	5680

RECEIVED
STATE CORPORATION COMMISSION
FEB 8 1993
CONSERVATION DIVISION
Wichita, Kansas