

15-119-00014-00-00

WLOG COPY


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company. GULF OIL CORPORATION
Farm. H. A. Holmes No. 1

SEC. 21 T. 33 R. 29W
C SE NW

Total Depth. 5924
Comm. 11-17-55 Comp. 12-31-55
Shot or Treated.
Contractor. Earl F. Wakefield
Issued. 4-14-56

County Meade
KANSAS



Elevation. 2600 DF

Production. 6,800,000 CFGPD

CASING:

13 3/8 @ 851' w/ 1300 sx cmt.
5 1/2 @ 5924' w/ 150 sx cmt.

Figures in Parentheses Bottom of Formations.

sand	430
red bed	560
sand	590
sand & red rock	800
red rock	950
sand	1420
sand & red bed	1505
red bed & salt	1648
anhydrite & shale	1840
shale & sand	1971
anhydrite & shale	2225
anhydrite, shale & red bed	2340
anhydrite	2390
anhydrite & lime	2515
anhydrite	2578
anhydrite & sand	2668
anhydrite & lime	2720
anhydrite & shale	2865
anhydrite & sand	2945
anhydrite, sand & lime	2977
chalk & lime	3033
sand & chalky lime	3054
chalk & lime	3145
shale & chalky lime	3294
chalky lime	3365
shale & chalky lime	3365
shale & lime	3658
chalky lime	3870
lime & shale, some chalk	3870
lime	3906
lime & shale	4010
lime & shale, some chert	4155
lime & shale	4226
shale & broken lime	4328
lime, shale & chert	4398
lime	4476
lime & shale	4564
lime, shale & chert	4610
lime & shale	4780
broken lime	4872
lime & shale	4950
lime	5003
shale & chalky lime	5073
shale & lime	5688
lime	5717
shale	5727
coring	5733
shale & sand streaks	5814
shale & some sand	5870
lime & shale	5924
Total Depth	

TOPS:	
Lovell	4410
Lansing	4544
Skiatook	5003
Cherokee	5397
Atoka-Morrow	5701
Morrow sand	5729
Mississippian	5811

RECEIVED
STATE CORPORATION COMMISSION
DEC 29 1969
CONSERVATION DIVISION
Wichita, Kansas

Perf. 4 JSPF/5740-66, fracked w/
20,000 gal kerosene, 30,000 lb sand,
preceded by 500 gals. mud acid.