

NORSEMAN DRILLING, INC.
WICHITA, KANSAS
DRILLERS' WELL LOG

WELL NAME: USA AQ-1H
SECTION 20-33S-40W
MORTON COUNTY, KANSAS

COMMENCED: JUNE 26, 1994

COMPLETED: JULY 01, 1994

OPERATOR: ANADARKO PETROLEUM CORPORATION

Depth		Formation	Remarks
From	To		
0	1299	Sand & Redbed	Ran jts of 24#
1300	1380	Glorietta Sand	8 5/8" csg set @
1381	3165	Redbed	753'; w/340 SX of 75/25 pozmix; 2% CC; 1/4# SX Floceal; Tailed with 150 SX Class H; 2% CC; 1/4# Floceal; Plug down 5:45 p.m. 06/27/94.

Ran 73 jts. 5 1/2" 15.50#, Set @ 3185'; Cement w/230
SX Premium; 2% CC; 1/4# Floceal; Tailed w/100 SX
Premium; 10# micro bond; 1% CC; 15# salt; 1/4# SX
Floceal; .06% Halad; Plug down @ 10:45 p.m. on
07/01/94.

STATE OF KANSAS)I, the undersigned, being duly sworn on
oath, state that the above Drillers' Well
Log is true and correct to the best of my
knowledge and belief and according to the
records of this office.


COUNTY OF SEDGWICK

NORSEMAN DRILLING, INC.

James P. Reilly
JAMES P. REILLY, PRESIDENT

Subscribed & sworn to before me this

July 6, 1994



My Appointment Expires:

June 15, 1995

Pamela A. Adamson
Pamela A. Adamson, Notary Public
340 Seville
Wichita, KS 67209

RECEIVED
STATE CORPORATION COMMISSION

OCT 26 1994

WICHITA, KANSAS