

RECEIVED

SEP 7 1982

CONSERVATION DIVISION
Wichita, Kansas

KANSAS

FORM CP-3
Rev. 1-8-82

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT REPORT

API Number 15-025-20 476-0000

200 Colorado Derby Building
Wichita, KS 67202

Operator's Full Name Wallace Oil & Gas Co

Complete Address 50 Pen Place Suite 250 Oklahoma City, Okla. 73118

Lease Name Randall Well No. 1

Location 660' E 1/4 - 1.2505' N 1/4 - NW/4 Sec. 31 Twp. 34 Rge. 21 (East)(West)

County Clark Total Depth 5700'

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated _____

Plugging Contractor Sargents Casing Pulling

Address Box 506, Liberal, Kansas License No. 511

Operation Completed: Hour: 5:30 PM Day: 1 Month: 7 Year: 1982

Plugging Operations attended by Agent?: All Part None

The above well was plugged as follows:

They ran 5696' of 4 1/2" production pipe & perforated from 5594' to 5652'. 1st plug Wallace Oil had squeezed off the perforations. 2nd plug 1000' with 35 sks of cement. 3rd plug 710' with 40 sks of cement. 4th plug 40' to 0' with 10 sks of cement on solid bridge. They recovered 4117' of 4 1/2" pipe. The plugging was accomplished by Sargents Casing Pulling

Amount of Surface Casing: 682 of 8 5/8" cement circulated

I hereby certify that the above plugging instructions were given as herein stated.

Signed: Paul A. Luthis
Conservation Division Agent

I hereby state that I was not present while the above well was being plugged, however, to the best of my knowledge and belief it was plugged as herein stated. A full account for my not being present is as follows:

Signed: _____
Conservation Division Agent

INVOICED

DATE 9-9-82

INV. NO. 1094-A