

KANSAS

STATE CORPORATION COMMISSION  
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION  
MAY 20 1968  
CONSERVATION DIVISION  
Wichita, Kansas

J. P. Roberts  
Administrator  
500 Insurance Building  
Wichita 2, Kansas

Operator's Full Name Knight Casing Pulling Co., Inc.

Complete Address: Box 405, Chase, Kansas 67524

Lease Name Campbell-Harper Trust Well No. 1

Location SW\*SW\*NE Sec. 29 Twp. 34 Rge. 21 (W)

County Clark Total Depth 5637'

Abandoned Oil Well X Gas Well      Input Well      SWD Well      D & A 8

Other well as hereafter indicated: None

Plugging Contractor: Knight Casing Pulling Co.

Address: Box 405, Chase, Kansas License No. 436

Operation Completed: Hour 11:00AM May 16 Month 5 Year 1968

The Above well was plugged as follows:

20" to 248' circulated w/ cement, 10" to 608' circulated w/ cement.

5 1/2" to 5620' cemented. Top perforations 5441'

Plug bottom w/ sand & 5 sacks cement, Top of cement 5200'

Mud 5200' to 600' Spotted 50 sacks cement 600' to 500'

Mud 500' to 60' Rock Bridge & 15 sacks cement 60' to 0'

Pulled 4473' of 5 1/2" casing.

I hereby certify that the above well was plugged as herein stated.

Signed: [Signature]  
Well Plugging Supervisor

INVOICED

DATE 5/20/68  
INV. NO. 4768-11