

Form CP-3  
Rev. 6-9-67

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION

AUG 25 1967

CONSERVATION DIVISION  
Wichita, Kansas

J. P. Roberts  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Intent to Drill,  
filed August 14, 1967.

Operator's Full Name W. C. Payne & Price Exploration Company

Complete Address 800 United Founders Tower, Oklahoma City, Oklahoma

Lease Name Georgia Well No. # 1

Location C NE SW Sec. 34 Twp. 28 Rge. 12 (E) (W) W

County Pratt Total Depth 4483'

Abandoned Oil Well      Gas Well      Input Well      SWD Well      D & A X

Other well as hereafter indicated     

Plugging Contractor Garvey Drilling Company

Address R. R. # 2, Great Bend, Kansas 67530 License No.     

Operation Completed: Hour 1:30 A.M. Day 24th Month August Year 1967

The above well was plugged as follows:

378' of 8 5/8" surface pipe, cement circulated with 350 sacks. Hole was  
filled with drilling mud to 300'; 1st cementing plug, bridged with 1 sack  
of dry cement and 1/2 sack of hulls on fluid at 300', and cemented with 19  
sacks, with cement from 290' to 230'. Hole was filled with drilling mud  
to 35', 2nd cementing plug, bridged with 1 sack of dry cement and 1/2 sack  
of hulls on fluid at 35', and cemented with 7 sacks, with cement from 25  
to the base of the cellar. Rat and mouse holes bridged and cemented with  
4 sacks.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Archie Elving  
Well Plugging Supervisor

DATE 8-28-67  
INV. NO. 6207-W