

KANSAS  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION

JUL 29 1963

CONSERVATION DIVISION  
Wichita, Kansas

J. P. Roberts  
Assitant Director  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

Operator's Full Name Skelly Oil Company

Complete Address: Box 649 Mc/Cook, Nebraska

Lease Name Cordes Well No. # 1

Location NW/4 NW/4 NW/4 Sec. 36 Twp. 33 Rge. 29 (E) (W)

County Meade Total Depth 5860'

Abandoned Oil Well X Gas Well      Input Well      SWD Well      D & A X

Other well as hereafter indicated:     

Plugging Contractor: Forbes Casing Pulling Co.

Address: Great Bend, Kansas License No. 49

Operation Completed: Hour 6 PM Day 24 Month 7 Year 63

The Above well was plugged as follows:

8 5/8" 1452' Circulated W/Cement. 5 1/2" Cemented. Plug Back to 5726'

Top Perforations 5690'

Sand 5726' to 5675' 20 Sax.cement 5675' to 5535'

Mud 5535' to 685' Rock Bridge 685' to 667'

35dSax.cement 667' to 567' Mud 567' to 40'

Rock Bridge 40' to 30' 10 SAX. Cement 30' to surface.

Pulled 2702' 5 1/2" Pipe. Company Pump. Weld Plate On Surface.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: [Signature]  
Well Plugging Supervisor

DATE 7/29/63  
INV. NO. 9494-W