

15-025-30076-0000

Form CP-3
Rev. 6-4-68

KANSAS



STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

RECEIVED
STATE CORPORATION COMMISSION

JAN 16 1973

CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Don C. Roder Oil Operations

Complete Address 104 W. Lockwood St., Medicine Lodge, Kansas 67104

Lease Name Grace E. Smith Well No. 1

Location C NW Sec. 14 Twp. 34 Rge. 22 (E) (W)

County Clark Total Depth 5700'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated None

Plugging Contractor Russ Casing Pulling.

Address Great Bend, Kansas License No. 623

Operation Completed: Hour 3:00 PM Day 12 Month 1 Year 1973

The above well was plugged as follows:

20" to 67' circulated w/ cement. 8 5/8" to 716' circulated w/ cement.

5 1/2" to 5700' cemented. Top perforations 5434'

Plug bottom w/ sand & 5 sacks cement. Top of cement 5350'

Mud 5350' to 550' Spotted 35 sacks cement 550' to 450'

Mud 450' to 45' Plug, Hulls & 15 sacks cement 45' to 0'.

Pulled 4210' of 5 1/2" casing.

I hereby certify that the above well was plugged as herein stated.

Signed: *Edward J. Lees*
Well Plugging Supervisor

INVOICED

DATE 1/16/73
INV. NO. 6859-4