

KANSAS

MP

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Administrator
500 Insurance Building
Wichita, Kansas 67202

Well Plugging Authority,
Original issued April 11, 1967
Renewal issued: July 18, 1967

Operator's Full Name Ashland Oil & Refining Company

Complete Address Box 18695, Oklahoma City, Oklahoma 73118

Lease Name Randell Well No. # 1-12

Location C N/2 C NW/4 Sec. 12 Twp. 34 Rge. 22 (E) (W) W

County Clark Total Depth 5546'

Abandoned Oil Well X Gas Well Input Well SWD Well D & A

Other well as hereafter indicated

Plugging Contractor Gayle E Toland & Company

Address Box 94336, Oklahoma City, Oklahoma License No. 539

Operation Completed: Hour 2:45 P.M. Day 18th Month July Year 1967

The above well was plugged as follows:

598' of 8 5/8" surface pipe, cement circulated. 5546' of 4 1/2" long string,
cemented with the top at 5165'. Top perforation 5400'. Baker cast iron plug
at 5310', and cemented with 2 sacks, through the dump bailer. 4800' of 4 1/2"
long string was recovered from the hole. 30 bbls. of drilling mud and 35 sacks
of cement was pumped into the 4 1/2" long string at 580', through a 4 1/2" swage.
Cement went on a vacuum, and column of cement was coasting in the hole. 4 hours
later the top of the cement was tagged at 570' in the surface pipe, bringing
cement plug from 675' to 570'. Hole was filled with mud to 45', and cemented
with 15 sacks to the base of the cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

JUL 20 1967

Signed: Audine Elving
Well Plugging Supervisor

DATE 7/20/67

CONSERVATION DIVISION
Wichita, Kansas
INV. NO. 6005-4