

Form CP-3
Rev. 6-4-68

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

OCT 23 1973

CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

Operator's Full Name Graham-Michaelis Corp.

Complete Address Box 247, Wichita, Kansas

Lease Name Randall Well No. 1-11

Location 50' W of Center Sec. 11 Twp. 34 Rge. 22 (E) (W)

County Clark Total Depth 5528'

Abandoned Oil Well Gas Well X Input Well SWD Well D & A

Other well as hereafter indicated

Plugging Contractor Lillard Casing Pulling

Address Woodard, Oklahoma License No. 618

Operation Completed: Hour 11:30 AM Day 17 Month 10 Year 1973

The above well was plugged as follows:

8 5/8" to 598' circulated w/ cement. 4 1/2" to 5527' cemented.

Top perforations 5370' Plug bottom w/ 20 sacks cement.

Top of cement 5200' Mud 5200' to 550'

Spotted 35 sacks cement 550' to 450' Mud 450' to 45'

Plug, Hulls & 15 sacks cement 45' to 0'. Company Pump

Pulled 4700' of 4 1/2" casing.

INVOICED

I hereby certify that the above well was plugged as herein stated.

DATE 10/23/73

INV. NO. 8053-10

Signed: Edgar J. Lewis
Well Plugging Supervisor