

10 KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

MAY 28 1963

CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Operator's Full Name Graham-Michaelis Drilling Co.

Complete Address: 211 North Broadway Wichita, Kansas

Lease Name Randall Well No. 1-23

Location SW SW SW Sec. 23 Twp. 34S Rge. 22 (E) (W)

County Clark Total Depth 5671'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated:

Plugging Contractor: Southwest Casing Pulling Co. Inc.

Address: Great Bend, Kansas License No. 399

Operation Completed: Hour 11 AM Day 25 Month 5 Year 63

The Above well was plugged as follows:

13" 580' Circulated w/cement. 5 1/2" 5670' Cemented. Perforations 5386' to 5394'

Plug bottom w/sand to 5370' 5 Sax.cement at 5370' Mud to 560'

Rock bridge 560' to 550' 50 sax.cement at 550' Mud to 40'

Rock bridge 40' to 30' 20 sax.cement 30' to surface.

Company Pump. Pulled 4790' 5 1/2" pipe.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Hugh Scott
Well Plugging Supervisor

DATE 5/28/63
INV. NO. 7154-W