

KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
OCT 1 1962
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Operator's Full Name Texaco Inc.

Complete Address: 614 Bitting Bldg., Wichita, Kansas

Lease Name Campbell "B" Well No. # 1

Location C SW NW Sec. 33 Twp. 34 Rge. 21 (E) (W)

County Clark Total Depth 5694'

Abandoned Oil Well Gas Well X Input Well SWD Well D & A

Other well as hereafter indicated:

Plugging Contractor: Comstock Pipe Pulling Inc.

Address: Stafford, Kansas License No. 490

Operation Completed: Hour 1 PM Day 27 Month 9 Year 62

The Above well was plugged as follows:

13 3/8" 156' Cemented. 8 5/8" 601' Cemented. 4 1/2" 5694' Cemented.

Perforations 5520' Bottom plug to 5500'

Heavy mud 5500' to 600' 10' bridge and 35 sax. cement 600' to 485'

Heavy mud 485' to 50' 10' bridge and 15 sax. cement 50' to surface.

(Company Pump) Pulled 4906' 4 1/2" pipe.

INVOICED

I hereby certify that the above well was plugged as herein stated.

DATE 10/31/62

INV. NO. 5481-W

Signed: [Signature]
Well Plugging Supervisor