

Y

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

RECEIVED
STATE CORPORATION COMMISSION
JUN 3 1968
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Knight Casing Pulling Co.

Complete Address: Box 405, Chase, Kansas

Lease Name Bentley Randell Well No. 1

Location C SW NE Sec. 32 Twp. 34 Rge. 21 (E) (W)

County Clark Total Depth 5680'

Abandoned Oil Well Gas Well X Input Well SWD Well D & A X

Other well as hereafter indicated: None

Plugging Contractor: Knight Casing Pulling Co.

Address: Box 405, Chase, Kansas License No. 436

Operation Completed: Hour 1:00PM Day 1 Month 6 Year 1968

The Above well was plugged as follows:

30" to 27' circulated w/ cement. 20" to 220' circulated w/ cement.

10 3/4" to 600' circulated w/ cement. 5 1/2" to 5620' cemented.

Top perforations 5448' Plug, bottom w/ sand & 5 sacks cement

Top of cement 5330' Mud 5330' to 500'

Rock bridge & 50 sacks cement 500' to 400' Mud 400' to 45'

Rock bridge & 15 sacks cement 45' to 0'

Pulled 3116' of 5 1/2" casing.

I hereby certify that the above well was plugged as herein stated.

Signed: Edgar G. Eves
Well Plugging Supervisor

INVOICED

DATE 6/4/68
INV. NO. 7864W