

15-025-10115-0000

Form CP-3
Rev. 6-26-62

KANSAS

Ty
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

RECEIVED
STATE CORPORATION COMMISSION
JUN 3 1968
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Knight Casing Pulling Co.

Complete Address: Box 405, Chase, Kansas

Lease Name Elmer V. Raddell Well No. 1

Location C NE SW Sec. 32 Twp. 34 Rge. 21 ~~(E)~~ (W)

County Clark Total Depth 5700'

Abandoned Oil Well Gas Well X Input Well SWD Well D & A X

Other well as hereafter indicated: None

Plugging Contractor: Knight Casing Pulling Co.

Address: Box 405, Chase, Kansas License No. 436

Operation Completed: Hour 3:00PM Day 1 Month 6 Year 1968

The Above well was plugged as follows:

30" to 30' circulated w/ cement. 20" to 245' circulated w/ cement.

10 3/4" to 605' circulated w/ cement. 4 1/2" to 5622' cemented.

Top perforations 5474' Plug bottom w/ sand & 4 sacks cement

Top of cement 5350' Mud 5350' to 600'

Rock bridge & 50 sackscement 600' to 500' Mud 500' to 45'

Rock bridge & 15 sacks cement 45' to 0'

Pulled 4022' of 4 1/2" casing.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Edgar J. Eves
Well Plugging Supervisor

DATE 6/13/68

INV. NO. 7865-W