

KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Administrator
500 Insurance Building
212 North Market
Wichita 2, Kansas

RECEIVED
STATE CORPORATION COMMISSION

SEP 20 1965

CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Sinclair Oil & Gas Co.

Complete Address: Box 2319 Pampa, Texas

Lease Name Randall Well No. # 1

Location C SE NW Sec. 32 Twp. 34 Rge. 21 (E) (W)

County Clark Total Depth 5610'

Abandoned Oil Well X Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated:

Plugging Contractor: Dazo Lease & Well Service

Address: Pampa, Texas License No. 138

Operation Completed: Hour 3 PM Day 16 Month 9 Year 65

The Above well was plugged as follows:

30'-28' Circulated w/cement. 20"-236' Circulated w/cement. 10 3/4"-Circulated w/cem

5 1/2"-5684'-Cemented. Top perforations 5498'. Plug bottom w/20 Sax.cement top
Cement at 4965'

Mud 4965' to 700' Spotted 50 Sax.cement 700' to 600'

Mud 600' to 50' Plug, 25 Sax.cement 50' to 0

Cut pipe off 3' below ground level and weld on plate.

Pulled 3518' 5 1/2" pipe. Company Pump.

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 9/20/65

INV. NO. 1825-W

Signed: [Signature]
Well Plugging Supervisor