

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-191-21860-00-01
Spot: SENWNW Sec/Twnshp/Rge: 22-34S-3W
990 feet from Section Line, 990 feet from Section Line
Lease/Unit Name: HUDSON Well Number: 1
County: SUMNER Total Vertical Depth: 4800 feet

KIOWA EXPI - DWWD
Operator License No.: 31925
Op Name: QUALITY WELL SERVICE, INC.
Address: 401 WEST MAIN
LYONS, KS 67554

Production Casing Size: 5.5 feet: 4776 \$156.00
Surface Casing Size: 8.625 feet: 297

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 09/17/2002 9:00 AM

Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.

Proposal Rcvd. from: RICHARD MCINTYRE Company: QUALITY WELL SERVICE, INC. Phone: (620) 727-3410

Proposed Plugging Method: According to KCC rules and regulations

RECEIVED
KCC DISTRICT #2
FEB 10 2003
WICHITA, KS

Plugging Proposal Received By: STEVE VANGIESON

Witness Type: Plugging Operations Partially Witnessed

Date/Time Plugging Completed: 09/17/2002 9:00 AM

KCC Agent: STEVE VANGIESON

Actual Plugging Report:

The Perfs were covered with sand tp 4260' and capped with 5 sks of cement. The casing was shot at 3606', 3409', and recovered from 3250'. The casing was pulled to 700', where 35 sks of cement was spotted. The casing was pulled to 350', where cement was circulated to surface. Pulled remaining casing.

Remarks: ALLIED CEMENTING 60/40 4% GEL

Plugged through: CSG

District: 02

Signed [Signature]
(TECHNICIAN)

INVOICED

DATE 2-11-03

INV. NO. 2003061184