

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-191-21860-00-01
Spot: SENWNW Sec/Twnshp/Rge: 22-34S-3W
990 feet from S Section Line, 990 feet from E Section Line
Lease/Unit Name: HUDSON Well Number: 1
County: SUMNER Total Vertical Depth: 4800 feet

Operator License No.: 31925
Op Name: QUALITY WELL SERVICE, INC.
Address: 401 WEST MAIN
LYONS, KS 67554

Conductor Pipe: Size feet: \$156.00
Surface Casing: Size 8.625 feet: 297 200 SX CMT
Production: Size 5.5 feet: 4776 110 SX CMT
Liner: Size feet:

Well Type: OIL UIC Docket No: Date/Time to Plug: 09/17/2002 9:00 AM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: JOE MAES Company: QUALITY WELL SERVICE Phone: (620) 727-3410

Proposed AS KCC REQUIERS.
Plugging
Method:

Plugging Proposal Received By: STEVE VANGIESON WitnessType: Plugging Operations Partially Witnessed
Date/Time Plugging Completed: 09/17/2002 9:00 AM KCC Agent: STEVE VANGIESON

Actual Plugging Report:

THE PERFS WERE SANDED BACK TO 4260' AND CAPPED WITH 5 SKS OF CEMENT. THE CASING WAS RECOVERED FROM 3200' AND PULLED TO 700', WHERE 35 SKS OF CEMENT WAS SPOTTED. THE CASING WAS PULLED TO 350', WHERE CEMENT WAS CIRCULATED TO SURFACE. PULLED REMAINING CASING AND TOPPED OFF THE CEMENT.

RECEIVED
KCC DISTRICT #2

SEP 25 2002

WICHITA, KS

Remarks: UNITED CEMENT INTG 60/40 4% GEL

Plugged through: CSG

District: 02

Signed _____

(TECHNICIAN)

INVOICED

DATE

10-11-02

INV. NO.

2003060632