

To: 1090910
STATE CORPORATION COMMISSION
Wichita, State Office Bldg. - PLUGGING SECTION
130 S. Market, Room 2078
Wichita, KS 67202

3-21

API NUMBER 15-129-21,553-0000
NW NE, SEC. 29, T 33 S, R 42 W/E
660 feet from NXX section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 9953

Operator: Harris Oil & Gas Co.
Name & Address 1125 Seventeenth St., Ste. 2290
Denver, CO 80202

RECEIVED
KANSAS CORP. CO.
Lease Name Rich Brown Well # 1-29
1998 MAR 27 A 11:35
County Morton 167,38

Well Total Depth 5150 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 9 5/8 feet 1365

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ O&A X

Other well as hereinafter indicated _____

Plugging Contractor Allen Drilling Co. License Number 5418

Address P.O. Box 1389, Great Bend, KS 67530

Company to plug at: Hour: _____ Day: 21 Month: 3 Year: 19 98

Plugging proposal received from Harold Frauli

(company name) Petroleum Management (phone) 316-624-8388

were: to fill hole with heavy mud and spot cement through drill pipe

1st plug at Hugoton/Council Grove with 100 sx cement,

2nd plug at 1370' with 70 sx cement, 3rd plug at 400' with 40 sx cement,

4th plug at 40' with 15 sx cement, 5th plug to circulate rathole with 15 sx cement,

6th plug to circulate mousehole with 10 sx cement.

Plugging Proposal Received by Steve Middleton
(TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None X

Operations Completed: Hour: 10:45 p.m. Day: 21 Month: 3 Year: 19 98

ACTUAL PLUGGING REPORT 1st plug at 2300' with 100 sx cement,

2nd plug at 1370' with 70 sx cement,

3rd plug at 400' with 40 sx cement,

4th plug at 40' with 15 sx cement,

5th plug to circulate rathole with 15 sx cement,

6th plug to circulate mousehole with 10 sx cement.

Remarks: Used 60/40 Pozmix 6% gel by Allied.

(If additional description is necessary, use BACK of this form.)

INVOICED

DATE 3-30-98

INV. NO. 50320

Signed [Signature]
(TECHNICIAN)