

15-129-10364-0000
R

1 060519

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- Comp. 5-29-55
NE NE SW, SEC. 34, T 33 S, R 42 W X

2310 feet from S section line
2970 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 6593

Lease Name McClain Well # 1-34

Operator: Coastal Oil & Gas Company

County Morton 104.20

Name & Address P. O. Box 1117

Well Total Depth 3206 feet

Elkhart, KS 67950

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 537 ✓

Abandoned Oil Well Gas Well X Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Halliburton Services License Number

Address P. O. Box 1598, Liberal, KS 67901

Company to plug at: Hour: 9:00 am Day: 21 Month: March Year: 19 85

Plugging proposal received from Bob Martin

(company name) Coastal Oil & Gas (phone) 316-697-2137

were: 5 1/2" at 3185.91' PBD 3186' Perfs at 2968-70'

1st plug ran tubing to 2315' and pumped 6 sx bulls and 25 sx cement

2nd plug filled hole with gel mud and pulled up to 1500' and spotted 52 sx cement.

came out of hole with tubing and pumped rubber plug to 430'. Lost circulateion in

5 1/2" but circulated 8 5/8".

Plugging Proposal Received by Paul A. Luthi (TECHNICIAN)

Plugging Operations attended by Agent?: All Part X None

Operations Completed: Hour: 12:45 pm Day: 25 Month: March Year: 19 85

ACTUAL PLUGGING REPORT 3-22-85 - 3rd plug ran tubing to 876' and pumped 100 gallons

flow check and 384 gallons tonblock 60. got circulation to surface and then spotted

158 sx cement at 780' filling annulus to surface. 3-25-85 - tagged plug in 5 1/2" at

570'. Circulated 70 sx cement through tubing filling hole to surface

RECEIVED
STATE CORPORATION COMMISSION

MAR 28 1985

Remarks: Used 60/40 Pozmix 2% gel 3% cc by Halliburton.

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this form.)

(did / ~~not~~) observe this plugging.

Signed Paul A. Luthi (TECHNICIAN)

DATE 4-3-85

INV. NO. 7492