

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-019-40036-00-00
Spot: SESENENW Sec/Twnshp/Rge: 5-34S-12E
4165 feet from S Section Line, 2824 feet from E Section Line
Lease Name: AMERICAN PETROLEUM Well #: 5
County: CHAUTAUQUA Total Vertical Depth: 1055 feet

Operator License No.: 5970

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	7	1050		0 SX
SURF	10	20		0 SX

Op Name: ELMORE, JOHN A. OR PATRICIA R.

Address: 776 HWY 99
SEDAN, KS 67361

Well Type: OIL

UIC Docket No:

Date/Time to Plug: 12/10/2014 12:00 AM

Plug Co. License No.: 32884

Plug Co. Name: ELMORE'S, INC.

Proposal Recvd. from: JOHN ELMORE

Company:

Phone: (620) 249-2519

Proposed Run 1" to bottom. Gel hole. Spot 20 sks cement. Perforate casing at 700' and at 350'. Run in 1" to 700'. Spot 5 sks cement.
Plugging Pull up to 350'. Cement to surface.
Method:

Plugging Proposal Received By: DUANE SIMS

WitnessType: PARTIAL

Date/Time Plugging Completed: 12/11/2014 12:00 PM

KCC Agent: DUANE SIMS

Actual Plugging Report:

Ran 1" to 1010' gelled hole and spotted 20 sack plug. Pulled 1" and perforated casing at 700' and 350'. Ran 1" back into 700' and spotted 15 sack plug. Pulled up to 350' and circulated cement to surface. Pulled 1" and topped well off. A total of 145 sacks of cement were used to plug this well.

Perfs:

RECEIVED
KCC DIST # 3
MAR 04 2015
CHANUTE, KS

DS

Remarks:

Plugged through: TBG

3-11-15 CKM

District: 03

Signed Quane A Sims
(TECHNICIAN)

Received
KANSAS CORPORATION COMMISSION

MAR 06 2015

CONSERVATION DIVISION
WICHITA, KS

Form CP-2/3