

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-095-21361-00-00  
Spot: SWNESE Sec/Twnshp/Rge: 10-29S-10W  
1980 feet from S Section Line, 660 feet from E Section Line  
Lease Name: NEISES Well #: 1  
County: KINGMAN Total Vertical Depth: 2703 feet

Operator License No.: 33055  
Op Name: KRUCKENBERG, GENE DBA CIRCLE K  
Address: 7317 NE STATE HWY K42  
ISABEL, KS 67065

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	2680		150 SX
PROD	4.5	2696		175 SXS CMT
SURF	8.625	332		275 SXS CMT
SURF	8.625	335		266 SX

Well Type: GAS UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 01/25/2015 12:00 AM

Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.

Proposal Rcvd. from: MIKE KELSO Company: MIKE'S TESTING & SALVAGE Phone: \_\_\_\_\_

Proposed Plugging Method: AS PER KCC RULES & REGS

Plugging Proposal Received By: JEFF KLOCK

WitnessType: PARTIAL

Date/Time Plugging Completed: 02/26/2015 4:00 PM

KCC Agent: B. J. HOPE

Actual Plugging Report:

SANDED BACK TO 2440' - CAPPED WITH 4 SXS CEMENT ON TOP. CUT CASING PIPE OFF @ 1805' PULLED CASING TO 1553' SPOTED 35 SXS CEMENT. PULLED CASING TO 965' SPOTED 35 SXS CEMENT. PULLED CASING TO 377' CIRCUALTED TO SURFACE WITH 125 SXS CLASS A CEMENT WITH 3% CC.

Perfs: \_\_\_\_\_

KCC WICHITA  
MAR 10 2015  
RECEIVED

Remarks: COPELAND CEMENTING OUT OF GREAT BEND, CLASS A CEMENT. PLUGGED DUE TO COMMISSION ORDER, PAST 10 YEARS NON-PRODUCTION & LOST LEASE.

Plugged through: CSG

3-11-15 CKM

District: 02

Signed

*B. J. Hope*

(TECHNICIAN)