

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-095-21619-00-01
Spot: SENWNWNW Sec/Twnshp/Rge: 4-30S-8W
4940 feet from S Section Line, 4880 feet from E Section Line
Lease Name: MOLITOR B Well #: 2
County: KINGMAN Total Vertical Depth: 3895 feet

Operator License No.: 3067
Op Name: MOLITOR OIL, INC.
Address: 9517 SW 80TH AVE
SPIVEY, KS 67142

String	Size	Depth (ft)	Pulled (ft)	Comments
PKR		3623		PACKER TYPE AND SETTING DEPTH: BAKER AD1 SET AT 3623
PROD	5.5	4407	2298	175 SX
SURF	8.625	299		75 SX
T1	2.875	3623		

Well Type: SWD UIC Docket No: D30540.0 Date/Time to Plug: 02/16/2015 12:00 AM
Plug Co. License No.: 5893 Plug Co. Name: PRATT WELL SERVICE, INC.
Proposal Rcvd. from: MARK MOLITOR Company: PRATT WELL SERVICE Phone: (620) 672-2531

Proposed Plugging Method: AS PER KCC RULES & REGS

Plugging Proposal Received By: B. J. HOPE Witness Type: PARTIAL
Date/Time Plugging Completed: 02/17/2015 4:00 PM KCC Agent: B. J. HOPE

Actual Plugging Report:

RAN TUBING INTO 3887' PUMPED 80 SX OF CLASS A CEMENT WITH 100 LBS OF HULLS & 3% CC. TAGGED TOC @ 3464' PUMPED 35 SXS OF CLASS A WITH 50 LBS OF HULLS & 3% CC. TAGGED TOC @ 3290'. CUT CASING PIPE OFF @ 2298' PULLED CASING. RAN TUBING INTO 1318' SPOTTED 35 SX OF CLASS A CEMENT. RAN TUBING TO 847' SPOTTED 35 SX OF CLASS A CEMENT. RAN TUBING INTO 345' CIRCULATED TO SURFACE WITH 250 SX OF CEMENT, THE FIRST 75 SX WERE CLASS A CEMENT FOLLOWED BY 175 SX OF 60/40 POZ MIX.

Perfs:

KCC WICHITA
MAR 10 2015
RECEIVED

Remarks: BASIC ENERGY OUT OF PRATT, KS. TICKET #12164. PLUGGED DUE TO FAILED MIT. HOLES IN CASING.

Plugged through: TBG

3/11/15 CKM

District: 02

Signed BJ Hope
cc: WIC

(TECHNICIAN)

ix