

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-125-30092-00-00  
Spot: SESWNE Sec/Twnshp/Rge: 1-34S-16E  
3017 feet from S Section Line, 1646 feet from E Section Line  
Lease Name: MCCOLLOUGH Well #: 1  
County: MONTGOMERY Total Vertical Depth: 1015 feet

Operator License No.: 33343  
Op Name: POSTROCK MIDCONTINENT PRODUC  
Address: OKLAHOMA TOWER 210 PARK AVE.  
OKLAHOMA CITY, OK 73102

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	4.5	1012		75 SX
SURF	7	85		65 SX

Well Type: CM UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 01/26/2015 12:00 AM  
Plug Co. License No.: 33749 Plug Co. Name: KEPLEY WELL SERVICE, LLC  
Proposal Rcvd. from: KEN PAULIE Company: \_\_\_\_\_ Phone: (620) 432-4200

Proposed Plugging Method: RUN TUBING TO TD, CEMENT THROUGH TUBING TO SURFACE, PULL TUBING OUT OF HOLE AND TOP WELL OFF W/ CEMENT.

Plugging Proposal Received By: \_\_\_\_\_ WitnessType: PARTIAL  
Date/Time Plugging Completed: 01/27/2015 12:00 AM KCC Agent: RUSSELL HINE

Actual Plugging Report:

Ran 2-3/8" to 1002' and pumped 10 bbls. Pulled out to 500' and pumped 5 bbl. Pulled to 250' and circulated cement to surface. Pulled all of cement string and hooked to 4-1/2". Squeezed and shut in at 400 psi. 168 sacks reported used by contractor.

Perfs:

Top	Bot	Thru	Comments
946	949		CIBP@760
703	707		

RECEIVED  
KCC DIST # 3  
MAR 04 2015  
CHANUTE, KS

RH

Remarks:

Plugged through: TBG

District: 03

Signed Russell Hine  
(TECHNICIAN)

3-11-15 ckm

Received  
KANSAS CORPORATION COMMISSION

MAR 06 2015

CONSERVATION DIVISION  
WICHITA, KS