

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-125-30446-00-00  
Spot: SWSWSE Sec/Twnshp/Rge: 25-33S-16E  
321 feet from S Section Line, 2350 feet from E Section Line  
Lease Name: FELTS Well #: 1-25  
County: MONTGOMERY Total Vertical Depth: 1040 feet

Operator License No.: 33343  
Op Name: POSTROCK MIDCONTINENT PRODUC  
Address: OKLAHOMA TOWER 210 PARK AVE.  
OKLAHOMA CITY, OK 73102

String	Size	Depth (ft)	Pulled (ft)	Comment
CIBP		750		
PROD	5.5	1040		140 SX
SURF	8.625	70		67 SX

Well Type: DH UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 01/27/2015 12:00 AM  
Plug Co. License No.: 33749 Plug Co. Name: KEPLEY WELL SERVICE, LLC  
Proposal Rcvd. from: KEN PAULIE Company: \_\_\_\_\_ Phone: (620) 432-4200

Proposed Plugging Method: RUN TUBING TO TF, CEMENT THROUGH TUBING TO SURFACE, PULL TUBING OUT OF HOLE & TOPE WELL OFF W/ CEMENT.

Plugging Proposal Received By: \_\_\_\_\_ WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 01/27/2015 12:00 AM KCC Agent: RUSSELL HINE

Actual Plugging Report:

Ran 2-3/8" to 1005'. Pumped 10bbl of portland. Pulled out to 500' and pumped 5bbl. Pulled out to 250' and circulated cement to surface. Pulled all of cement string and hooked to 4-1/2" and squeezed. Shut in at 250psi. 161 sacks reported used by contractor.

Perfs:

Top	Bot	Thru	Comments
959	962		
750	750		
518	522		
481	483		

RECEIVED  
KCC DIST # 3  
MAR 04 2015  
CHANUTE, KS

RH

Remarks:

Plugged through: TBG

District: 03

Signed Russell Hine  
(TECHNICIAN)

3-11-15 CKM

Received  
KANSAS CORPORATION COMMISSION

Form CP-2/3

MAR 06 2015

CONSERVATION DIVISION  
WICHITA, KS