

STATE OF KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
200 Colorado Derby Building
Wichita, Kansas 67202

15-189-20405-0000
RECEIVED
KANSAS CORPORATION COMMISSION
03/92

JUN 10 1996

WELL PLUGGING APPLICATION FORM
(PLEASE TYPE FORM and File ONE Copy)

CONSERVATION DIVISION
WICHITA, KS

API # 15-189-20,405-0000 (Identifier number of this well). This must be listed for wells drilled since 1967; if no API# was issued, indicate spud or completion date.

WELL OPERATOR ANADARKO PETROLEUM CORPORATION KCC LICENSE # 4549
(owner/company name) (operator's)

ADDRESS P.O. BOX 351 CITY LIBERAL

STATE KANSAS ZIP CODE 67905-0351 CONTACT PHONE # (316) 624-6253

LEASE SPIKES "C" WELL# 1 SEC. 02 T. 33S R. 38 (XXXX/West)

- NE- NE - SE SPOT LOCATION/QQQQ COUNTY STEVENS

2590 FEET (in exact footage) FROM S/X (circle one) LINE OF SECTION (NOT Lease Line)

150 FEET (in exact footage) FROM E/X (circle one) LINE OF SECTION (NOT Lease Line)

Check One: OIL WELL GAS WELL D&A SWD/ENHR WELL DOCKET# _____

CONDUCTOR CASING SIZE _____ SET AT _____ CEMENTED WITH _____ SACKS

SURFACE CASING SIZE 8-5/8" SET AT 1719' CEMENTED WITH 800 SACKS

PRODUCTION CASING SIZE 4-1/2" SET AT 6215' CEMENTED WITH 810 SACKS

LIST (ALL) PERFORATIONS and BRIDGEPLUG SET: 6036-45, 6052-62, DV TOOL SET AT 3145

ELEVATION 3154' NA T.D. 6417' PBTD 6130' ANHYDRITE DEPTH NA
(G.L./K.B.) (Stone Corral Formation)

CONDITION OF WELL: GOOD POOR _____ CASING LEAK _____ JUNK IN HOLE _____

PROPOSED METHOD OF PLUGGING MIRU CSG PULLERS.MIX AND PMP 2 SK HULLS AND 20 SK CMT PLUG FROM 6100-5900'.DISPLACE W/9 PPG MUD.PULL ON 4-1/2" CSG,LOCATE FREE POINT AND SHOOT OFF.SPOT 30 SK CMT PLUG AT CUT OFF POINT.PULL 4-1/2" CSG TO 1775'. SPOT 75 SK CMT PLUG FROM 1800-1600'. TOH W/4-1/2" CSG & SPOT 10 SK CMT PLUG FROM 30-3'.CUT OFF 8-5/8" CSG 3' BELOW GROUND LEVEL AND CAP.INScribe WELL NAME AND NUMBER, LEGAL DESCRIPTION AND PLUGGING DATE ON CAP.RDMO CSG PULLERS.RESTORE LOCATION.

(If additional space is needed attach separate page)

IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED? IS ACO-1 FILED? YES _____

If not explain why? _____

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 et. seq. AND THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

LIST NAME OF COMPANY REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS:

DAVID GILMORE PHONE# (316) 544-7240

ADDRESS P.O. BOX 208 City/State HUGOTON, KANSAS 67951

PLUGGING CONTRACTOR SARGENT & HORTON PLUGGING, INC. KCC LICENSE # 31151
(company name) (contractor's)

ADDRESS RT 1, BOX 49BA, TYRONE, OK 73951-9731 PHONE # (405) 854-6515

PROPOSED DATE AND HOUR OF PLUGGING (If Known?) UPON APPROVAL

PAYMENT OF THE PLUGGING FEE (K.A.R. 82-3-118) WILL BE GUARANTEED BY OPERATOR OR AGENT

DATE: 6-3-96 AUTHORIZED OPERATOR/AGENT: J.L. Ashton
(signature) DIV. PROD. MGR.



JAMES L. ASHTON
DIVISION PRODUCTION MANAGER

June 7, 1996

Kansas Corporation Commission
Conservation Division
Finney State Office Building
130 South Market, Rm 2078
Wichita, Kansas 67202

Attn: Priscilla Zadoka

Re: Plug and Abandonment
Well Plugging Application Form (Form CP-1)

Spikes "C" No. 1
Section 2-33S-38W
Stevens County, Kansas

Dear Ms. Zadoka:

Enclosed in duplicate is a well plugging application (KCC Form CP-1) submitted for your approval to plug and abandon the above referenced well. Upon approval of the application, please notify Anadarko's Liberal office at the letterhead address so that plugging operations may commence.

Very truly yours,


A handwritten signature in cursive script, appearing to read "J. L. Ashton".

J. L. Ashton
Division Production Manager
BJW/sh

Enclosures

cc: Well File
Ken Lester - HGO
Manager Land Administration - HGO
WI Owners

kccintpa.wp6





Kansas Corporation Commission

Bill Graves, Governor Timothy E. McKee, Chair Susan M. Seltam, Commissioner John Wine, Commissioner
Judith McConnell, Executive Director David J. Heinemann, General Counsel

NOTICE OF RECEIPT OF WELL PLUGGING APPLICATION (CP-1)

June 10, 1996

Anadarko Petroleum Corporation
P O Box 351
Liberal KS 67905-0351

Spike "C" #1
API 15-189-20,405
2590 FSL 150 FEL
Sec. 02-33S-38W
Stevens County

Dear David Gilmore,

This letter is to notify you that the Conservation Division is in receipt of your plugging proposal, form CP-1, for the above-captioned well.


Your CP-1 has been reviewed by the Conservation Division central office for completeness and to verify license numbers. The plugging proposal will now be forwarded to the district office listed below for review of your proposed method of plugging.

Please contact the district office for approval of your proposed plugging method at least at five (5) days before plugging the well, pursuant to K.A.R. 82-3-113 (b). If a workover pit will be used during the plugging of the well it must be permitted. A CDP-1 form must be filed and approved prior to the use of the pit.

The Conservation Division's review of form CP-1, either in the central or district office, does not include an inquiry into well ownership or the filing operator's legal right to plug the well.

This notice in no way constitutes authorization to plug the above-captioned well by persons not having legal rights of ownership or interest in the well. This notice is void after ninety (90) days from the above date.

Sincerely,


 David P. Williams
 Production Supervisor

District: #1
304 W. McArtor
Dodge City, KS 67801
(316) 225-6760