

STATE OF KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
200 Colorado Derby Building
Wichita, Kansas 67202

FORM CP-1
Rev. 2/89

WELL PLUGGING APPLICATION FORM
(File One Copy)

API NUMBER 15-189-20,401,000 (of this well).
(This must be listed; if no API# was issued, please note drilling completion date.)

WELL OWNER/OPERATOR Anadarko Petroleum Corporation OPERATOR'S LICENSE NO. 4549

ADDRESS P.O. Box 351, Liberal, Kansas 67905-0351 PHONE # (316) 624-6253

LEASE (FARM) Troup "B" WELL NO. 2 WELL LOCATION 1050' ENL & 1250' FEL COUNTY Stevens

SEC. 9 TWP. 33S RGE. 38 ~~(E)~~Dr(W) TOTAL DEPTH 6205 PLUG BACK TD 6094

Check One:

OIL WELL GAS WELL D & A SWD or INJ WELL DOCKET NO. _____

SURFACE CASING SIZE 8 5/8 SET AT 1701 CEMENTED WITH 600/200 SACKS

CASING SIZE 4 1/2 SET AT 6203 CEMENTED WITH 400/200 2nd Stage SACKS
DV Tool @ 3100'

PERFORATED AT 6049-62 (Morrow)

CONDITION OF WELL: GOOD POOR CASING LEAK JUNK IN HOLE

PROPOSED METHOD OF PLUGGING (1) Set CIBP @ 6000' (on wireline) & dump 2 sxs cmt on top.

(2) Load hole with fresh water. (3) TIH w/tbg to 1850' & circulate heavy mud back to surface.

(4) Spot 30 sxs common cmt @ 1850. (5) Spot 30 sxs common cmt @ 1000'. (over)

(If additional space is needed use back of form.)

IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED? No IS ACO-1 FILED? Yes
(If not explain.) Already on file w/KCC

DATE AND HOUR PLUGGING IS DESIRED TO BEGIN Upon KCC approval

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 et. seq. AND THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

NAME OF REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS: O. J. Stuck

PHONE # (316) 544-7240

ADDRESS P.O. Box 208, Hugoton, Kansas 67951

PLUGGING CONTRACTOR Sargents Casing Pulling Service LICENSE NO. 6547

ADDRESS Box 506, Liberal, Kansas 67905-0506 PHONE # (316) 624-7455

PAYMENT OF THE PLUGGING FEE (K.A.R. 82-3-118) WILL BE GUARANTEED BY OPERATOR OR AGENT.

SIGNED: M. L. Pease
(Operator or Agent) M. L. Pease

DATE: 5/13/90 Division Production Mg

RECEIVED
STATE CORPORATION COMMISSION
MAY 15 1990
CONSERVATION DIVISION
Wichita, Kansas

(6) Spot 5 sxs common cmt @ 50'. (7) Hook up to bradenhead & pump 150 sxs common cmt.
Note: If unable to pump into @ 800# then shut down & close in bradenhead. (8) Cut-off casing 3' below ground level & weld on cap. (9) Restore location and move off surface equipment.



Kansas Corporation Commission

MIKE HAYDEN GOVERNOR
KEITH R. HENLEY CHAIRMAN
RICH KOWALEWSKI COMMISSIONER
JACK SHRIVER COMMISSIONER
JUDITH MCCONNELL EXECUTIVE DIRECTOR
FRANK A. CARO, JR. GENERAL COUNSEL

CONSERVATION DIVISION
SHARI FEIST ALBRECHT, DIRECTOR
200 Colorado Derby Bldg.
202 W. 1st Street
Wichita, KS 67202-1286
(316) 263-3238

NOTICE OF RECEIPT OF
WELL PLUGGING APPLICATION

July 17, 1990

Anadarko Petroleum Corporation
P.O. Box 351
Liberal, KS 67905-0351

Troup "B" #2
1050'FNL-1250'FEL 09-33-38W
Stevens County, KS
API No. 15-189-20,401

Gentlemen:

This letter is to notify you that the Conservation Division is in receipt of your plugging proposal, form CP-1, for the above-captioned well.

Your CP-1 has been reviewed by the Conservation Division central office for completeness and to verify license numbers. The plugging proposal will now be forwarded to the district office listed below for review of your proposed method of plugging. Please contact the district office to review your proposed plugging method at least five (5) days before plugging the well, pursuant to K.A.R. 82-3-113(b). Failure to do so is punishable by an administrative penalty of up to \$1000.

It has recently come to my attention that the form CP-1 has been filed by operators other than the owner or operator of the well and without the consent of the owner or operator. The Conservation Division's review of form CP-1, either in the central or district office, does not include an inquiry into well ownership or the filing operator's legal right to plug the well. The CP-1 is simply reviewed to determine compliance with plugging rules and regulations.

This notice in no way constitutes authorization to plug the above-captioned well by persons not having legal rights of ownership or interest in the well. This notice is void after ninety (90) days from the above date.

Sincerely,

David P. Williams

David P. Williams
Production Supervisor

District: #1, 304 W. McArtor
Dodge City, KS 67801