

DISTRICT CONSERVATION AGENT'S REPORT

R

TO:

State Corporation Commission
Conservation Division
800 Bitting Building
Wichita, Kansas

FILE NO. 150-3

LOCATION NE NE SW

SEC. 5 TWP. 34 RGE. 43

Dry Hole X Abandoned Oil Well _____ Abandoned Gas Well _____

I have this date completed supervision of plugging of:

Well No. 1-5 Lease Williams

Operator Panhandle Eastern Pipe Line Co. Address Box 351, Liberal, Kansas

Field Greenwood County Morton

Total Depth 3400 Feet.

Plugging Contractor Daco Well Service Company

Plugging Contractor's License No. 138

Address Borger, Texas

(Describe briefly the manner in which the well was plugged)

During completion of well all producing zones which had been perforated were squeezed with cement. 10-3/4" Casing set @ 581' was left in the well. The 7" OD casing was shot off @ 1336' and pulled. The hole filled with mud to 600' where 15 sacks of cement was spotted. The remaining hole filled with mud and a cap of 10 sacks of cement was placed in the top of surface casing.

RECEIVED
STATE CORPORATION COMMISSION
OCT 19 1955
CONSERVATION DIVISION
Wichita, Kansas

R. J. Phillips
District Conservation Agent

Date 10-17-55

PLUGGING
FILE SEC-2 T-34 R-43W
BOOK PAGE 150 LINE 3