

KANSAS



STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202


RECEIVED
STATE CORPORATION COMMISSION
DEC 21 1971
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Anadarko Production Company
Complete Address Box 351, Liberal, Kansas
Lease Name Linscott "B" Well No. 2
Location App C N/2 SW Sec. 32 Twp. 34 Rge. 43 ~~85~~ (W)
County Morton Total Depth 4630'
Abandoned Oil Well X Gas Well _____ Input Well _____ SWD Well _____ D & A X
Other well as hereafter indicated None
Plugging Contractor Sargents Casing Pulling Co.
Address Box 506, Liberal, Kansas License No. 511
Operation Completed: Hour 2:00PM Day 13 Month 12 Year 1971

The above well was plugged as follows:

8 5/8" to 1242' circulated w/ cement. 4 1/2" to 4260' cemented.
Top perforations 4196' Plug bottom w/ 25 sacks cement
Top of cement 3600' Mud 3600' to 1000'
Spotted 35 sacks cement 1000' to 900' Mud 900' to 45'
Plug, Halls & 15 sacks cement 45' to 0'. Company Pump
Pulled 2600' of 4 1/2" casing.

I hereby certify that the above well was plugged as herein stated

Signed: 
Well Plugging Supervisor

INVOICED

DATE 1-10-72

INV. NO. 4904-W