

15-175-10155-0000

STATE OF KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
200 Colorado Derby Building
Wichita, Kansas 67202

FORM CP-1
Rev. 6/4/84

WELL PLUGGING APPLICATION FORM
(File One Copy)

API NUMBER NA completed 9/25/64 (of this well) 8/88
(This must be listed; if no API# was issued, please note drilling completion date.)

LEASE OPERATOR Anadarko Petroleum Corporation OPERATORS LICENSE NO. 4549

ADDRESS P. O. Box 351, Liberal, Kansas 67905-0351 PHONE # (316) 624-6253

LEASE (FARM) CONDT UNIT WELL NO. 2-1 WELL LOCATION C NW SE COUNTY Seward

SEC. 12 TWP. 34S RGE. 33 ~~(E)~~ (W) TOTAL DEPTH 6325 PLUG BACK TD 5910 (CIBP)

Check One:

OIL WELL GAS WELL D & A SWD or INJ WELL X DOCKET NO. C-16,786

SURFACE CASING SIZE 8-5/8" SET AT 1616' CEMENTED WITH 850 SACKS

CASING SIZE 4-1/2" SET AT 6324' CEMENTED WITH 175 SACKS

PERFORATED AT 6254-57 5963-91

CONDITION OF WELL: GOOD X POOR CASING LEAK repaired JUNK IN HOLE

OPERATOR'S SUGGESTED METHOD OF PLUGGING THIS WELL Spot 10 sacks cement on CIBP @ 5910. Fill hole with mud to 3042, shoot off at freepoint and spot 30 sacks cement across cut off. Spot 50 sacks cement 1666'-1566' and spot 15 sacks cement from 40'-0'. Cap well

(If additional space is needed use back of form)

IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED? Yes IS ACO-1 FILED? Log Filed
(If not, explain) Originally filed under name of WORTHINGTON "B" No.1

DATE AND HOUR PLUGGING IS DESIRED TO BEGIN ASAP

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 et seq AND THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

NAME OF COMPANY REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS Jerry Ruttman PHONE # (316) 624-6253

ADDRESS P. O. Box 351, Liberal, Kansas 67905-0351

PLUGGING CONTRACTOR Sargents Casing Pulling Service LICENSE NO.

ADDRESS 620 S. Lincoln, Liberal, Kansas 67901 PHONE # (316) 624-7455

PAYMENT WILL BE GUARANTEED BY OPERATOR OR AGENT SIGNED: M. L. Pease
(Operator or Agent)

M. L. Pease, Division Production Manager

DATE: 12/7/87

RECEIVED
STATE CORPORATION COMMISSION
DEC 14 1987
12-14-87
CONSERVATION DIVISION
6547 Wichita, Kansas

①

State of Kansas



Kansas Corporation Commission

MIKE HAYDEN
KEITH R. HENLEY
RICH KOWALEWSKI
MARGALEE WRIGHT
JUDITH MCCONNELL
FRANK A. CARO, JR.

GOVERNOR
CHAIRMAN
COMMISSIONER
COMMISSIONER
EXECUTIVE DIRECTOR
GENERAL COUNSEL

CONSERVATION DIVISION
SHARI M. FEIST, DIRECTOR
200 Colorado Derby Bldg.
202 W. 1st Street
Wichita, KS 67202-1286
(316) 263-3238

THIS NOTICE

December 17, 1987

MAR 17 '88

WELL PLUGGING NOTICE

EXPIRES

Condit Unit #2-1 (SWD)
C NW SE
Sec. 12-34S-33W
Seward County

Anadarko Petroleum Corporation
P. O. Box 351
Liberal, KS 67905

Gentlemen:

This is your notice to plug the above subject well in accordance with the Rules and Regulations of the State Corporation Commission.

Please contact the district office listed below to review your suggested method of plugging five days prior to plugging the well (KAR-82-3-113).

This notice is void after ninety (90) days from the above date.

Sincerely,

Shari Feist

Shari Feist
Director
State Corporation Commission

DISTRICT #1 302 W. McArtor, Dodge City, KS 67801 (316) 225-6760