

15-175-20953-0000

STATE OF KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
200 Colorado Derby Building
Wichita, Kansas 67202

FORM CP-1
Rev. 6/4/84

WELL PLUGGING APPLICATION FORM
(File One Copy)

API NUMBER 15-175 - 20,953 - 60⁰⁰ (of this well)
(This must be listed; if no API# was issued, please note drilling completion date.)

LEASE OPERATOR Anadarko Petroleum Corporation OPERATORS LICENSE NO. 4549
ADDRESS P. O. Box 351, Liberal, Kansas 67905-0351 PHONE # (316) 624-6253
1250 FNL
LEASE (FARM) Hatcher "A" WELL NO. 1 WELL LOCATION 1330 FWL COUNTY Seward
SEC. 12 TWP. 34 RGE. 33 (E) or (W) TOTAL DEPTH 2800 PLUG BACK TO Surface

Check One:

OIL WELL _____ GAS WELL _____ D & A x SWD or INJ WELL _____ DOCKET NO. _____
SURFACE CASING SIZE 8 5/8 SET AT 698 CEMENTED WITH 350 SACKS
CASING SIZE 5 1/2 SET AT 2799 CEMENTED WITH 225 SACKS
PERFORATED AT 2629 -34 (Herington) 2658-68 (Krider)

CONDITION OF WELL: GOOD x POOR _____ CASING LEAK _____ JUNK IN HOLE _____

OPERATOR'S SUGGESTED METHOD OF PLUGGING THIS WELL Plugs pumped down casing; 1 sx cottonseed hulls & 20' sxs cmt 2668' - 2540', pmp 30 sxs cmt 1300' - 1020', cut off 5 1/2" csg @ 792', pmp 50 sxs cmt 760'-610', pushed wooden plug to 40' w/10 sxs cmt 40'-5', Cement type: 60/40 POZ mix w/6% gel. Heavy drilling mud spotted between each plug.
(If additional space is needed use back of form)

IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED? Yes IS ACO-1 FILED? Yes
(If not, explain)

DATE AND HOUR PLUGGING IS DESIRED TO BEGIN 7/19/87

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 et seq AND THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

NAME OF COMPANY REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS:
Jim Barlow PHONE # (316) 624-6253
ADDRESS P. O. Box 351, Liberal, Kansas 67905-0351

PLUGGING CONTRACTOR Sargent's Casing Pulling Service LICENSE NO. 6547
ADDRESS 620 S. Lincoln, Liberal, Kansas 67901 PHONE # (316) 624-7455

PAYMENT WILL BE GUARANTEED BY OPERATOR OR AGENT SIGNED: M. L. Pease
(Operator or Agent)
M. L. Pease, Division Production Manager
DATE: 9/2/87

RECEIVED
STATE CORP. COM. DIVISION
9-4-87
SEP 4 1987