

RECEIVED

MAR 04 2003

KCC WICHITA

FORM CP-11(2/92)

STATE OF KANSAS  
KANSAS CORPORATION COMMISSION  
CONSERVATION DIVISION  
130 South Market - Room 2078  
Wichita, Kansas 67202

**WELL PLUGGING APPLICATION FORM**  
(PLEASE TYPE FORM and File ONE Copy)

API # 15-175-21887-0000 (Identifier number of this well). This must be listed for wells drilled since 1967; if no API# was issued, indicate spud or completion date.

WELL OPERATOR Raydon Exploration, Inc. KCC LICENSE # 30604  
(owner/company name) (operator's)  
ADDRESS 9400 N. Broadway, Ste. 400 CITY Oklahoma City

STATE OK ZIP CODE 73114 CONTACT PHONE # (620) 624-0156

LEASE Max WELL# 1-28 SEC. 28 T. 34S R. 31 (East/West)

- NW - NE - NW SPOT LOCATION/OQQO COUNTY Seward

505 FEET (in exact footage) FROM S (N) (circle one) LINE OF SECTION (NOT Lease Line)

1650 FEET (in exact footage) FROM E (W) (circle one) LINE OF SECTION (NOT Lease Line)

Check One: OIL WELL  GAS WELL  D&A  SWD/ENHR WELL  DOCKET# \_\_\_\_\_

CONDUCTOR CASING SIZE 20" SET AT 40' CEMENTED WITH 6 sack grout SACKS

SURFACE CASING SIZE 8-5/8" SET AT 1665' CEMENTED WITH 515 SACKS

PRODUCTION CASING SIZE 4-1/2" SET AT 5283' CEMENTED WITH 50 SACKS

LIST (ALL) PERFORATIONS and BRIDGEPLUG SETS: 5208-5220', CIBP 5200', 4562-4568',

ELEVATION 2682/2694 T.D. 6450 PBDT 5257 ANHYDRITE DEPTH \_\_\_\_\_  
(G.L./K.B.) (Stone Corral Formation)

CONDITION OF WELL: GOOD  POOR  CASING LEAK  JUNK IN HOLE

PROPOSED METHOD OF PLUGGING Pump 200 sacks hulls followed with 25 sacks cement to 2600', shoot pipe off at 2000', lay down to 1700', fill hole with mud, pump 50 sacks cement plug from 1700-1600', lay down pipe to 600', pump 40 sack (If additional space is needed attach separate page) plug from 600-500',

IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED? Yes IS ACO-1 FILED? Yes

If not explain why? \_\_\_\_\_

**PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 et. seq. AND THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.**

LIST NAME OF COMPANY REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS:

Keith Hill, Crown Consulting, Inc. PHONE# (620) 624-0156

ADDRESS PO Box 1816 City/State Liberal, KS 67905-1816

PLUGGING CONTRACTOR Sargent & Horton Plugging, Inc. KCC LICENSE # 31151

ADDRESS Rt. 1, Box 49BA, Tyrone, OK 73954 PHONE # 580 854-6515

PROPOSED DATE AND HOUR OF PLUGGING (If Known?) 4-01-03

**PAYMENT OF THE PLUGGING FEE (K.A.R. 82-3-118) WILL BE GUARANTEED BY OPERATOR OR AGENT**

DATE: 3-03-03 AUTHORIZED OPERATOR/AGENT: [Signature]  
(signature)

12/03

1/04



15-175-21887-0000

## Kansas Corporation Commission

*Kathleen Sebelius, Governor John Wine, Chair Cynthia L. Claus, Commissioner Brian J. Moline, Commissioner*

### NOTICE OF RECEIPT OF WELL PLUGGING APPLICATION (CP-1)

Raydon Exploration, Inc.  
9400 N. Broadway #400  
Oklahoma City, OK 73114

March 04, 2003

Re: MAX #1-28  
API 15-175-21887-00-00  
S2NWNENW 28-34S-31W, 505 FNL 1650 FWL  
SEWARD COUNTY, KANSAS

Dear Operator:

This letter is to notify you that the Conservation Division is in receipt of your plugging proposal, form CP-1, for the above-captioned well.

Your CP-1 has been reviewed by the Conservation Division central office for completeness and to verify license numbers. The plugging proposal will now be forwarded to the district office listed below for review of your proposed method of plugging.

**Please contact the district office for approval of your proposed plugging method at least five (5) days before plugging the well, pursuant to K.A.R. 82-3-113 (b). If a workover pit will be used during the plugging of the well it must be permitted. A CDP-1 form must be filed and approved prior to the use of the pit.**

The Conservation Division's review of form CP-1, either in the central or district office, does not include an inquiry into well ownership or the filing operator's legal right to plug the well.

**This notice in no way constitutes authorization to plug the above-captioned well by persons not having legal rights of ownership or interest in the well. This notice is void after ninety (90) days from the above date.**

District: #1  
210 E Frontview, Suite A  
Dodge City, KS 67801  
(316) 225-8888

Sincerely

A handwritten signature in black ink, appearing to read "David P. Williams".

David P. Williams  
Production Supervisor