

STATE OF KANSAS  
STATE CORPORATION COMMISSION

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
212 North Market, Insurance Bldg.  
Wichita, Kansas

WELL PLUGGING RECORD

Meade County, Sec. 4 Twp. 34 Rge. ~~28~~ 29 (W)

Location as "NE/CNW%SW%" or footage from lines 330' Fr. N and 330' Fr. E Line

Lease Owner Diamond Shamrock Corporation

Lease Name Irvin Vogt "B" Well No. 1

Office Address Box 631, Amarillo, Texas 79105

Character of Well (completed as Oil, Gas or Dry Hole) Oil

Date well completed April 15 1959

Application for plugging filed October 8, 1968

Application for plugging approved 19

Plugging commenced October 15, 1968


Plugging completed October 15, 1968

Reason for abandonment of well or producing formation No longer capable of oil production in commercial quantity.

If a producing well is abandoned, date of last production October 1968

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

NORTH



Locate well correctly on above Section Plat

Name of Conservation Agent who supervised plugging of this well \_\_\_\_\_

Producing formation Morrow Sand Depth to top 5790 Bottom 5797 Total Depth of Well 5878 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Morrow Sand	Oil	5790'	5797'	9 5/8"	1540'	-0-
				5 1/2"	5877.5'	3,018'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Spotted 20 sacks cement from 5,697' to 5,797'

40 sacks cement from 800' to 900'

10 sacks cement from 5' to 30'.

Filled balance of hole with mud.

Spotted 20 sacks cement from 5,697; to 5,797'. Pulled 5 1/2" casing to 900' and spotted 40 sacks cement. Displaced with 20 barrels of 9.5# mud - good circulation. Recovered 3,018' of 5 1/2" casing. Spotted 10 sacks cement from 5' to 30'. Welded steel cap on top of surface casing.

RECEIVED  
DEC 2 1968  
CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Daco Lease and Well Service

Address 1700 S. Main, Borger, Texas

STATE OF Texas, COUNTY OF Potter, ss.

W. W. Killingsworth (employee of owner) or (owner/contractor) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) W. W. Killingsworth

Box 631, Amarillo, Texas 79105

(Address)

SUBSCRIBED AND SWORN TO before me this 29th day of November, 19 68

Pauline Powell

PAULINE POWELL  
Notary Public

Notary Public.

My commission expires 6-1-69



IRVIN J. VOGT #B-1  
NE NW NE - 4-34S-29W  
MEADE COUNTY, KANSAS

Operation Commenced 2-17-59  
Operation Completed 3-20-59

FORMATION RECORD

0 - 160	Red Bed & Sand
160 - 756	Shale & Sand
756 - 1545	Red Bed & Sand
1545 - 1823	Shale & Shells
1823 - 1968	Shale & Lime Shells
1968 - 2197	Shale & Shells
2197 - 2304	Shale & Lime Shells
2304 - 2402	Lime
2402 - 2478	Lime & Shale
2478 - 2565	Sandy Lime
2565 - 2664	Lime
2664 - 2694	Sandy Lime
2694 - 2755	Lime
2755 - 2817	Lime
2817 - 2929	Lime & Shale
2929 - 2983	Lime
2983 - 3052	Lime
3052 - 3118	Lime
3118 - 3196	Lime
3196 - 3290	Lime & Sand
3290 - 3375	Lime & Shale
3375 - 3462	Lime & Shale
3462 - 3583	Lime & Shale
3583 - 3655	Lime & Chalk
3655 - 3718	Lime & Shale
3718 - 3840	Lime & Shale
3840 - 3959	Shale & Lime - Strks.
3959 - 4082	Shale & Lime
4082 - 4263	Lime, Shale & Sand
4263 - 4400	Lime & Shale
4400 - 4485	Shale & Lime
4485 - 4601	Lime & Shale
4601 - 4685	Lime
4685 - 4716	Lime
4716 - 4807	Lime
4807 - 4820	Lime
4820 - 4885	Lime
4885 - 4941	Lime
4941 - 4985	Lime

RECEIVED  
STATE CORPORATION COMMISSION  
DEC 2 1968  
CONSERVATION DIVISION  
Wichita, Kansas

Page #2

Irvin J. Vogt #B-1

4985 - 5004	Lime
5004 - 5050	Lime
5050 - 5110	Lime
5110 - 5155	Lime & Shale
5155 - 5197	Lime & Shale
5197 - 5255	Lime & Shale
5255 - 5283	Lime
5283 - 5339	Lime & Shale
5339 - 5393	Lime & Shale
5393 - 5396.006	Lime
5396 - 5422	Lime
5422 - 5454	Lime
5454 - 5473	Lime
5473 - 5508	Lime
5508 - 5548	Lime
5548 - 5582	Lime
5582 - 5612	Lime
5612 - 5649	Lime
5649 - 5669	Lime
5669 - 5713	Lime
5713 - 5751	Lime
5751 - 5801	Core #1
5801 - 5851	Core #2 (Morrow Sand)
5851 - 5871	Lime
5871	Total Depth

RECEIVED  
STATE CORPORATION COMMISSION  
DEC 2 1968  
CONSERVATION DIVISION  
Wichita, Kansas

CASING RECORD

- 2-20-59 Ran 49 jts. 9-5/8" OD 8 rd. thd. Rge. 2 Cond. A 32# H40 casing, set at 1539' KB cemented with 900 sacks 2% c.c. Plug down at 7:00 A.M. KB to GL 12'.
- 3-17-59 Ran 189 jts. 5-1/2" casing, set at 5878' KB. Cemented with 85 sacks cement. Plug down at 3:28 A.M.

# DACO LEASE & WELL SERVICE

1700 S. MAIN BR 3-7321 BORGER, TEXAS

HYDRAULIC CASING PULLING • ROUSTABOUTS • DITCH DIGGING



RECEIVED  
STATE CORPORATION COMMISSION  
DEC 2 1968  
CONSERVATION DIVISION  
Wichita, Kansas

### AFFIDAVIT OF FACT

TO WHOM IT MAY CONCERN:

THIS IS TO CERTIFY THAT DACO LEASE & WELL SERVICE DID CEMENT THE BELOW NAMED WELL AS INSTRUCTED, AND IN ACCORDANCE WITH RAILROAD COMMISSION OF TEXAS SPECIFICATIONS AS SHOWN BELOW.

NAME OF OPERATOR Diamond Shamrock Corporation  
ADDRESS Attn: Bill Killingsworth Box 631 Amarillo, Texas  
LEASE NAME Irvin Vogt WELL NO. B-1  
COUNTY Meade County, Kansas

<u>20</u>	SACKS CEMENT FROM	<u>5697</u>	TO	<u>5797</u>
<u>40</u>	SACKS CEMENT FROM	<u>800</u>	TO	<u>900</u>
<u>10</u>	SACKS CEMENT FROM	<u>5</u>	TO	<u>30</u>
_____	SACKS CEMENT FROM	_____	TO	_____

KEN D. DAVIS

BEFORE ME, THE UNDERSIGNED AUTHORITY ON THIS DAY PERSONALLY APPEARED KEN D. DAVIS, KNOWN TO ME TO BE THE PERSON WHOSE NAME IS SUBSCRIBED TO THIS INSTRUMENT AND THAT HE HAS KNOWLEDGE OF ALL THE FACTS STATED HEREIN.

SUBSCRIBED AND SWORN TO BEFORE ME THIS 20 DAY OF November A.D. 19 68 HUTCHINSON COUNTY, TEXAS.