


STATE OF KANSAS  
STATE CORPORATION COMMISSION

Form CP-4

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
212 No. Market  
Wichita, Kansas 67202

WELL PLUGGING RECORD



Meade County, Sec. 2 Twp. 34S Rge. (E) 29 (W)  
Location as "NE/CNW/SW" or footage from lines. C SE SW  
Lease Owner Clinton Oil Company  
Lease Name E. Cordes "A" Well No. 1  
Office Address 217 N. Water, Wichita, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole  
Date well completed July 20, 1972  
Application for plugging filed 19  
Application for plugging approved 19  
Plugging commenced July 20, 1972  
Plugging completed July 20, 1972  
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes (Edgar Eyes)

Name of Conservation Agent who supervised plugging of this well  
Producing formation Depth to top Bottom Total Depth of Well 5900 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
	Surface	0	1538'	8-5/8"	1538'	None
	Casing					

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.


Heavy Mud from Total Depth to 1100 Feet,  
35 sax Plug from 1100 Feet to 1000 Feet;  
Heavy Mud to 45 Feet, 1/2 sax Halls, Plug  
Bridged and 15 sax Cement to Base of  
Cellar; 2 sax Cement in Rat Hole.  
Job completed @ 8:30 A.M.

RECEIVED  
STATE CORPORATION COMMISSION  
JUL 27 1972  
7-27-72  
CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)  
Name of Plugging Contractor Sun Oil Well Cementing Co.  
Address Box 169, Great Bend, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.  
Clarence Michael of Sage Drilling Co. (employee of owner) or owner or operator of the above described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above described well as filed and that the same are true and correct. So help me God.

(Signature) Clarence Michael  
500 Bitting Bldg., Wichita, Kansas  
(Address)



SUBSCRIBED AND SWORN TO before me this 25th day of July 1972  
Louise K. Whitted  
Notary Public.  
My commission expires November 26, 1974.

DRILLERS LOG

E. CORDES "A" NO. 1

CASING RECORD:	OPERATOR: Clinton Oil Company	DESCRIPTION:
8-5/8" @ 1538' w/640 sax cement	CONTRACTOR: Sage Drilling Co.	C SE SW Sec. 2-34S-29W Meade County, Kansas.
TOTAL DEPTH: 5900'	COMMENCED: July 7, 1972	
	COMPLETED: July 20, 1972	

<u>FORMATION</u>	<u>FROM</u>	<u>TO</u>	<u>REMARKS</u>
Surface Soil & Sand	0	490	
Shale, Sand & Gyp	490	1380	
Shale	1380	2547	
Lime & Shale	2547	3726	
Shale	3726	3942	
Shale & Lime	3942	4178	
Lime & Shale	4178	4725	
Lime, Shale & Chert	4725	4830	
Lime & Shale	4830	5119	
Lime	5119	5320	
Lime & Shale	5320	5900	D&A

RECEIVED  
STATE CORPORATION COMMISSION  
JUL 27 1972  
CONSERVATION DIVISION  
Wichita, Kansas

I certify that this is a true and correct copy of the above log to the best of my knowledge.

SAGE DRILLING CO., INC.

BY Clarence Michael  
Clarence Michael



Subscribed and sworn to before me this 25th day of July, 1972.

Louise K. Whitted  
Louise K. Whitted, Notary Public

My commission expires:  
November 26, 1974.