

API NUMBER 15-119-20211

LEASE NAME Keltner - 0000

WELL NUMBER 1

687 Ft. from (S) Section Line

688 Ft. from (W) Section Line

SEC. 31 TWP. 34 RGE. 28 (N) or (W)

COUNTY Meade

Date Well Completed 5-6-98

Plugging Commenced 5-5-98

Plugging Completed 5-6-98

EASE OPERATOR Cretaceous Energy Inc

ADDRESS 4925 Greenville Ave #1010 DALLAS, TX 75206

PHONE#(214) 692-7092 OPERATORS LICENSE NO. 31807

Character of Well D & A

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 5-5-98 (date)

by SCOTT ALBERG (KCC District Agent's Name).

Is ACO-1 filed? Yes If not, is well log attached? _____

Producing Formation NONE Depth to Top _____ Bottom _____ T.D. _____

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
<u>Wireford</u>	<u>Water</u>	<u>0'</u>	<u>1354'</u>	<u>8 5/8"</u>	<u>1354'</u>	<u>0'</u>
<u>Council Grove</u>	<u>Water</u>					
<u>Lansing</u>	<u>Water</u>	<u>0'</u>	<u>3372'</u>	<u>4 1/2"</u>	<u>3372'</u>	<u>2697'</u>
<u>Manitou</u>	<u>Water</u>					
<u>MISSISSIPPIAN</u>	<u>Water</u>					

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug material were used, state the character of same and depth placed, from _____ feet to _____ feet each section. Mixed 1 SK hulls to 20 SK cmt. to plug perfs from 3233 to 3033. Recovered 2697 ft. 4 1/2. Pulled to 1380 & mixed 50 SK plug 1380 to 1230. Pull to 500 & mixed 50 SK 500 to 350. Mixed 10 SK plug 40' to 0. Cut off & capped 8 5/8 4 ft. below ground level.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Sargent And Horton Plugging, Inc. License No. 31151

Address Rt. 1, Box 49 BA Tyrone, OK 73951-9731

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: CRETACEOUS ENERGY INC (fees paid)


STATE OF TEXAS COUNTY OF DALLAS, ss.

Henry S. Anderson (Employee of Operator) or (Operator) above-described well, being first duly sworn on oath, says: That I have knowledge of the facts and statements, and matters herein contained and the log of the above-described well as filed to the same are true and correct, so help me God.

(Signature) Henry S. Anderson

(Address) 4925 Greenville Ave #1010, Dallas TX 75206

AND SWORN TO before me this 4th day of June, 1998
Jeannie Denman
 Notary Public



My Commission Expires: _____