

15-119-2009-0000

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas

WELL PLUGGING RECORD

Meade County, Sec. 24 Twp. 34S Rge. 29W (E) (W)

Location as "NE/CNW/SW" or footage from lines C SW/4

Lease Owner Nelson B. Escue

Lease Name Merkle Well No. 1-24

Office Address 23 East 11th, Liberal, Kansas 67901

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed August 21 19 67

Application for plugging filed August 21 19 67

Application for plugging approved August 21 19 67

Plugging commenced August 21 19 67

Plugging completed August 21 19 67

Reason for abandonment of well or producing formation

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Edgar J. Evers - Box F, Sublette, Kansas

Producing formation Depth to top Bottom Total Depth of Well 3330 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	663'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Mud from 3330' to 700'  
Plugged @ 700' with 35 Sacks Cement  
Plugged @ 35' to Surface with 15 Sacks Cement

RECEIVED  
STATE CORPORATION COMMISSION  
SEP 6 1967  
CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Earl F. Wakefield

Address 300 West Douglas - Suite 500, Wichita, Kansas 67202

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.

Fred S. Barker (employee of owner) or (owner) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Fred S. Barker

300 West Douglas - Wichita, Kansas (Address)

Subscribed and sworn to before me this 28th day of August, 19 67

Wanda W. Riley Notary Public. My commission expires January 25, 1969



LEASE: MERKLE #1-24  
OWNER: NELSON B. ESCUE  
CONT: EARL F. WAKEFIELD  
COMM: 8-14-67  
COMP: 8-21-67

LOCATION: C SW/4  
SECTION 24-34S-29W  
MEADE COUNTY, KANSAS  
CASING: 8 5/8" SET @ 663'

Surface Clay	100
Sand, Red Bed & Anhydrite	665
Red Bed & Anhydrite	945
Anhydrite - Shale	1415
Shale	1745
Shale & Lime	2200
Lime & Shale	2325
Lime	3141
Lime & Shale	3305
Shale	3330
R.T.D.	3330

RECEIVED  
STATE CORPORATION COMMISSION  
SEP 6 1967  
CONSERVATION DIVISION  
Wichita, Kansas

STATE OF KANSAS |  
                          |  
COUNTY OF SEDGWICK |      SS

I, FRED S. BARKER, DO HEREBY CERTIFY THAT THE ABOVE IS A TRUE AND  
CORRECT COPY OF THE DRILLER'S LOG ON THE MERKLE #1-24, LOCATED  
C SW/4 OF SECTION 24-34S-29W, MEADE COUNTY, KANSAS.

EARL F. WAKEFIELD

BY Fred S. Barker  
Fred S. Barker

TESTED AND SWORN TO BEFORE ME THIS 28TH DAY OF AUGUST, 1967.



COMMISSION EXPIRES:  
AUGUST 25, 1969

Wanda W. Riley  
WANDA W. RILEY      NOTARY PUBLIC