

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-129-20715-0000

LEASE NAME Witcher C

WELL NUMBER 2

SPOT LOCATION NW SW NW

SEC. 30 TWP. 33 RGE. 42 ~~XXXX~~ (W)
1880' FNL, 560' FWL

COUNTY Morton

Date Well Completed 8-20-84

Plugging Commenced 8-20-84

Plugging Completed 8-20-84

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Cities Service Oil & Gas Corp.

ADDRESS 3545 N.W. 58th St., Okla. City, OK 73112

PHONE # (405) 949-4400 OPERATORS LICENSE NO. 5447

Character of Well D & A
(Oil, Gas, D&A, SWD, (Input, Water Supply Well))

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? #6

Is ACO-1 filed? Yes If not, is well log attached? _____

Producing formation None Depth to top _____ bottom T.D. 5000'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8-5/8"	1355'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state, the character of same and depth placed, from feet to feet each set. Ran OE DP to 4630' and spotted following open hole cement plugs: 35 sx 4630-4530' 75 sx 3085-2885' 40 sx 1419-1319' base surf., 35 sx 648-498' middle surf. 15 sx 40'-4' top hole. Cement was 60/40 pozmix, 2% total gel and 3% Ca Cl.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Wakefield Drilling License No. 677
Address P.O. Box 548, Winfield, Kansas 67156-0548

STATE OF Oklahoma COUNTY OF Oklahoma, ss.

Delbert G. Oliver (employee of operator) ~~xxx~~
operator of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

RECEIVED
CORPORATION COMMISSION

(Signature) Delbert G. Oliver

(Address) 3545 NW 58th St.

(Address) Okla. City, Ok 73112

2-13-84
SEP 13 1984

SUBSCRIBED AND SWORN TO before me this 6th day of Sept., 19 84

CONSERVATION DIVISION
Wichita, Kansas

Joey S. Carter
Notary Public

My Commission expires: 6-12-88