


STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to
Conservation Division
State Corporation Comm.,
245 North Water
Wichita, KS 67202

Seward County, Sec. 9 Twp. 34S Rge. 31W E/W
Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines
1980 FNL 1980 FWL

Lease Owner Cabot Corporation
Lease Name Hayes Well No. 1
Office Address Box 509, Guymon, Oklahoma
Character of Well (Completed as Oil, Gas or Dry Hole)
Gas



Locate well correctly on above
Section Plat

Date Well completed July 3, 1964
Application for plugging filed August 27, 1979
Application for plugging approved August 30, 1979
Plugging commenced September 26, 1979
Plugging completed September 28, 1979
Reason for abandonment of well or producing formation
Depleted

If a producing well is abandoned, date of last production
April 1979

Was permission obtained from the Conservation Division or
its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Bill Owens
Producing formation Morrow Depth to top 5666 Bottom 5677 Total Depth of Well 5827
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Morrow	Gas	5658	5678	8 5/8	1400	None
				4 1/2	5827	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

- Hole Loaded w/9.2# Mud
- Plug #1 Pump 25 sks. of cement @ 5400 to 5677
- Plug #2 Pump 40 sks. of cement @ 1400 to 1300
- Plug #3 Put 10 sks. of cement @ 40 to 0
- Cut off 8 5/8" Csg. and capped.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Sargent's Casing Pulling Service, Box 506, Liberal, Kansas 67901

STATE OF TEXAS COUNTY OF GRAY, ss.
Ray Wooldridge (employee of owner) or (owner/owner's representative)

of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) *Ray Wooldridge*
P. O. Box 1101, Pampa, Texas 79065
(Address)

SUBSCRIBED AND SWORN TO before me this 19th day of October, 1979

Evaughn Bowemmon
(Evaughn Bowemmon) Notary Public.

My commission expires January 11, 1980

RECEIVED
OCT 22 1979 10-22-79
CONSERVATION DIVISION
Wichita, Kansas

15-175-10161-0000

1980' FROM THE NORTH LINE
AND 1980' FROM THE WEST LINE
SECTION 9-34S-31W
SEWARD COUNTY, KANSAS

Received
from GMM

HAYS WELL #1

CONTRACTORS: THE R. W. RINE DRILLING COMPANY

STARTED: JUNE 8, 1964

COMPLETED: JUNE 27, 1964

L O G

Sand & Red Bed	0'	-	768'
Red Bed & Gypsum	768'	-	1400'
Shale & Anhydrite	1400'	-	2235'
Anhydrite & Gypsum & Shale	2235'	-	2475'
Lime & Shale	2475'	-	2637'
Anhydrite & Lime	2637'	-	2819'
Lime & Shale	2819'	-	3090'
Lime	3090'	-	3400'
Lime & Shale	3400'	-	3575'
Lime	3575'	-	3920'
Lime & Shale	3920'	-	4642'
Lime	4642'	-	4730'
Lime & Shale	4730'	-	4879'
Lime	4879'	-	5084'
Lime & Shale	5084'	-	5126'
Lime	5126'	-	5235'
Lime & Shale	5235'	-	5278'
Lime	5278'	-	5376'
Lime & Shale	5376'	-	5620'
Lime, Shale, Sand	5620'	-	5702'
Lime	5702'	-	5712'
Lime & Shale	5712'	-	5910'
Lime	5910'	-	6050'

Totco @ 770', 1/4°; @ 1117', 1/4°;
@ 1400', 1/4°; 8 5/8" @ 1400/800
sx. poz. + 100 sxs. reg.
Totco @ 2167', 1/2°

Totco @ 2880', 1/4°
Totco @ 3290', 1/2°

Totco @ 3920', 3/4°; @ 4422', 1°
Totco @ 4730', 3/4°

Totco @ 5020', 1°

Totco @ 5240', 1°

Totco @ 5520', 1°

4 1/2" @ 5829'

RECEIVED
STATE CORPORATION COMMISSION
AUG 29 1979
CONSERVATION DIVISION
Wichita, Kansas

STATE OF KANSAS)
COUNTY OF SEDGWICK) ss

I, R. M. Green, do hereby certify that the above is a true and accurate log of the Hays Well #1, located 1980' from the north line and 1980' from the west line, section 9-34S-31W, Seward County, Kansas.

Young

R. M. Green
R. M. Green, Secy.-Treas.

Subscribed and sworn to before me this 2nd day of July, 1964.

RECEIVED
JUL 6 1964
CABOT CORPORATION
OIL & GAS

Loren E. Lake
Loren E. Lake, Notary Public

My Commission Expires: 6/14/66

[Signature]