

STATE OF KANSAS  
 STATE CORPORATION COMMISSION  
 Finney State Office Building  
 130 South Market, Rm 2078  
 Wichita, Kansas 67202

WELL PLUGGING RECORD  
 K.A.R.-82-3-117

15-175-10143-0001  
 API NUMBER NA (SPUD 9/23/64)

LEASE NAME DAVIES "D"

WELL NUMBER 1

1980 Ft. from N Section Line

1980 Ft. from E Section Line

SEC. 08 TWP. 34S RGE 31 ( E ) or ( W )

COUNTY SEWARD

Date Well Completed 10/28/64

Plugging Commenced 02/27/97

Plugging Completed 03/04/97

TYPE OR PRINT  
 NOTICE: Fill out completely  
 and return to Cons. Div.  
 office within 30 days

LEASE OPERATOR ANADARKO PETROLEUM CORPORATION

ADDRESS P.O. BOX 351, LIBERAL, KS 67901-0351

PHONE # ( 316 ) 624-6253 OPERATORS LICENSE NO. 4549

Character of Well GAS

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 02/20/97 (date)

by MR. GARY WINTERS & MR. STEVE MIDDLETON (KCC District Agent's Name)

Is AC0-1 filed? YES If not, is well log attached? \_\_\_\_\_

Producing Formation L. MORROW Depth to Top 5608' Bottom 5674' T.D. 6050'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
L. MORROW	GAS	5608'	5674'	8-5/8"	1449'	4'
				4-1/2"	6047'	6047'

Describe in detail, the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set. MIRU SARGENT & HORTON PLUGGING, INC. HLS DMPD 2 SXS CMT ON RETAINER @ 5580', SHOT 4-1/2" CSG LOOSE @ 1528', PULLED TO 1480', PMPD 50 SXS CMT 1480-1330', PULLED TO 600', MIXED & PMPD 40 SXS CMT 600-500', PULLED PIPE. PMPD 10 SXS CMT 40-0' CUT OFF & CAPPED 8-5/8" CSG. 4' BELOW GL. WITNESSED BY STATE REP GARY WINTERS & MR. STEVE MIDDLETON.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor SARGENT & HORTON PLUGGING, INC. License No. 31151

Address RT. 1, BOX 498A, TYRONE, OK 73951-9731 PHONE: (405) 854-6515

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: ANADARKO PETROLEUM CORPORATION

STATE OF KANSAS COUNTY OF SEWARD, ss.

JOHN A. BROMAN, DIVISION PRODUCTION ENGINEER (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) John A. Broman

JOHN A. BROMAN, DIVISION PRODUCTION ENGINEER

(Address) P.O. BOX 351, LIBERAL, KS 67901-0351

SUBSCRIBED AND SWORN TO before me this second day of April, 1997

FREDA L. HINZ  
 Notary Public - State of Kansas  
 My Commission Expires 5-15-99

Freda L. Finney  
 Notary Public