


STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD API # - None

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to
Conservation Division
State Corporation Comm.
245 North Water
Wichita, KS 67202

Seward County, Sec. 6 Twp. 34S Rge. 31 E/W
Location as "NE/CNW1/4SW1/4" or footage from lines
1250' FSL & 1250' FWL of Sec. 6
Lease Owner Gulf Oil Corporation
Lease Name Robert Davies Well No. 1
Office Address P. O. Box 12116, Okla. City, OK, 73157
Character of Well (Completed as Oil, Gas or Dry Hole)
Oil
Date Well completed Nov. 24 19 61
Application for plugging filed May 24 19 83
Application for plugging approved June 13 19 83
Plugging commenced Sept. 3 19 83
Plugging completed Sept. 16 19 83
Reason for abandonment of well or producing formation
unecon to produce



If a producing well is abandoned, date of last production
December 30 19 63

Was permission obtained from the Conservation Division or
its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Paul Luthi
Producing formation Morrow Depth to top 5714 Bottom 5724 Total Depth of Well 6133
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Morrow	oil	5714	5724	8 5/8"	1487	none
				4 1/2"	5901	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

MIRU Barlow WSU. POH w/rod & tbg, RIH w/2-3/8" tbg to 5865', MIRU Howco, spot 50 sk Cl H cmt f/5865-5287'. POH w/tbg to 5286', circ 4 1/2" csg full w/78 bbl 9 ppg mud, POH w/tbg. MIRU Dia-Log, cut csg @1587'. POH to 1542', spot 100 sk Cl A cmt f/1542-1421'. POH w/4 1/2" csg, top off 8-5/8" csg f/43' to sfc w/10 sk Cl H cmt. Cut 8-5/8" csg off 6' BGL, weld cap, ID well, repair loc, Well P & A 9/16/83. Last Well on Lease.
State man, Paul Luthi was contacted before & during the plug'g, he approved the procedure but was not on location.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Barlow Well Service LIC #6690

STATE OF OKLAHOMA COUNTY OF OKLAHOMA, ss.
Dorretta Moore (employee of ~~Barlow Well Service~~ operator)
of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Dorretta Moore
P. O. Box 12116, Okla. City, OK, 73157
(Address)

SUBSCRIBED AND SWORN TO before me this 19th day of October, 19 83

Patricia A. Wonderly
Notary Public.

My commission expires 01-31-87

Wichita-Kansas
CONSERVATION DIVISION

RECEIVED
STATE CORPORATION COMMISSION

OCT 21 1983

OCT 2 1983

RECEIVED
STATE CORPORATION COMMISSION

CONSERVATION DIVISION
Wichita, Kansas

LEASE: ROBERT DAVIES #1
OPERATOR: GULF OIL CORP.
CONTRACTOR: EARL F. WAKEFIELD
COMM: 10-28-61 COMP: 11-24-61

LOCATION: C SW SECTION 6-34S-31W
SEWARD COUNTY, KANSAS
CASING: 8 5/8" Set at 1487'
4 1/2" Set at 6133'

Conductor	85
Sand	252
Sand and Shale	953
Red Bed	1270
Lime	1340
Lime, Anhydrite	1487
Shale	1741
Shale and Lime	2412
Lime and Shale	2550
Lime	2760
Lime and Shale	2854
Lime	3032
Lime and Chalk	3124
Lime	3657
Shale	4030
Shale and Lime	4190
Shale with streaks lime	4270
Shale and Lime	4346
Lime	4380
Lime	4530
Lime and Shale	4615
Lime	4821
Lime with streaks shale	4924
Lime	5327
Lime and Shale	5650
Shale and Lime	5715
Sand	5740
Sand and Lime	5815
Lime and Shale	5945
Lime	6000
Lime and Shale	6020
Lime	6133
T.D.	6133

STATE OF KANSAS)
) ss
COUNTY OF SEDGWICK)

I hereby certify that the above is a true and correct copy of the log on the ROBERT DAVIES #1 well, located C SW, Section 6-34S-31W, Seward County, Kansas.

EARL F. WAKEFIELD

By _____

Subscribed and sworn before me this 6th day of December, 1961.

My commission expires:
January 25, 1965

NOTARY

RECEIVED
STATE CORPORATION COMMISSION

MAY 27 1983

CONSERVATION DIVISION
Wichita, Kansas